

# UNIFORM STANDARD DETAILS for PUBLIC WORKS CONSTRUCTION

SPONSORED and DISTRIBUTED  
by the

MARICOPA ASSOCIATION  
OF  
GOVERNMENTS

METRIC

ARIZONA

## 100 SERIES GENERAL INFORMATION

101	GENERAL INFORMATION
110	PLANS SYMBOLS
112	DIMENSIONING FOR ROAD IMPROVEMENT PLANS
120-1	SURVEY MARKER
120-2	SURVEY MARKER (SURVEY FOR UNINCORPORATED AREAS OF COUNTY)
130	BARRICADE
131	STREET SIGN BASE
135-1	STEEL GUARD RAIL
135-2	STEEL GUARD RAIL
135-3	STEEL GUARD RAIL
135-4	STEEL GUARD RAIL
140	SAFETY POST
150	PRECAST SAFETY CURB
160	1830 mm CHAIN LINK FENCE AND GATE
170	TYPICAL RUNWAY OR TAXIWAY LIGHTING DETAIL
190	ROCK CORRECTION PROCEDURE FOR MAXIMUM DENSITY DETERMINATION

## 200 SERIES STREET INFORMATION

200	BACKFILL, PAVEMENT AND SURFACE REPLACEMENT
201	PAVEMENT SECTION AT TERMINATION
202	ALLEY DETAILS (PAVED AND UNPAVED)
203	SCUPPER
204	EQUIPMENT CROSSING
205	PAVED TURNOUTS
206-1	CONCRETE SCUPPER
206-2	CONCRETE SCUPPER
220	CURB AND GUTTER - TYPES 'A', 'B', 'C', AND 'D'
221	CURB AND GUTTER (TRANSITION, INTEGRAL AND WARNING BEACON)
222	SINGLE CURB - TYPES 'A', 'B' AND TERMINATION
223	MEDIAN NOSE TRANSITION
224	JOINT FOR DRAINAGE INLETS AND MANHOLE COVERS
230	SIDEWALKS
231	SIDEWALK RAMPS - TYPE 'A'
232	SIDEWALK RAMPS - TYPE 'B'
233	SIDEWALK RAMPS - TYPE 'C'
234	SIDEWALK RAMPS - TYPE 'D'
240	VALLEY GUTTERS
250	DRIVEWAY ENTRANCES
251	RETURN TYPE DRIVEWAYS
252	BUS AND PARKING BAYS
260	ALLEY ENTRANCE (WITH COMBINED CURB AND GUTTER)
261	ALLEY ENTRANCE (WITH ROLL TYPE CURB AND GUTTER)
262	WING TYPE ALLEY ENTRANCE (WITH COMBINED CURB AND GUTTER)
263	WING TYPE ALLEY ENTRANCE (WITH ROLL TYPE CURB AND GUTTER)
270	FRAME AND COVER AND GRADE ADJUSTMENTS

## 300 SERIES WATER INFORMATION

301	BLOCKING FOR WATER GATE AND BUTTERFLY VALVES
303-1	JOINT RESTRAINT FOR DUCTILE IRON AND POLYETHYLENE WRAPPED DUCTILE IRON WATER PIPES
303-2	JOINT RESTRAINT FOR DUCTILE IRON AND POLYETHYLENE WRAPPED DUCTILE IRON WATER PIPES
310	CAST IRON WATER METER BOX COVER NO. 1
311	CAST IRON WATER METER BOX COVER NO. 2
312	CAST IRON WATER METER BOX COVER NO. 3
313	CAST IRON WATER METER BOX COVER NO. 4
314	CAST IRON WATER METER BOX COVER NO. 5
320	CONCRETE WATER METER BOX
321	STANDARD WATER METER VAULT
340	INSTALLING TAPPING SLEEVES AND VALVES
345-1	75 mm, 100 mm, 150 mm WATER METER
345-2	100 mm, 150 mm, WATER METER WITH ON-SITE FIRE HYDRANTS
346	FIRE LINE DETECTOR CHECK VAULT
360	FIRE HYDRANT INSTALLATION
362	LOCATIONS FOR NEW HYDRANTS
370	VERTICAL REALIGNMENT OF WATER MAINS
380	THRUST BLOCKS FOR WATER LINES
381	ANCHOR BLOCKS FOR VERTICAL BENDS
389	CURB STOP WITH VALVE BOX AND COVER
390	CURB STOPS WITH FLUSHING PIPE
391-1	VALVE BOX INSTALLATION AND GRADE ADJUSTMENTS
391-2	VALVE BOX INSTALLATION
392	DEBRIS CAP INSTALLATION

## 400 SERIES SEWER INFORMATION

402	ENCASED PIPE FOR CANAL CROSSINGS
403-1	PIPE SUPPORTS ACROSS TRENCHES
403-2	PIPE SUPPORTS ACROSS TRENCHES
403-3	ALTERNATE TO PIPE SUPPORT
404	WATER AND SANITARY SEWER CROSSING
405	BROKEN SEWER LINE REPLACEMENT
420	PRECAST CONCRETE SEWER MANHOLE
421	OFFSET MANHOLE FOR 200 mm - 750 mm PIPE
422	SEWER MANHOLE AND COVER FRAME ADJUSTMENT
423	WATER TIGHT 760 mm MANHOLE FRAME AND COVER
424	610 mm AND 760 mm MANHOLE FRAME AND COVER
425	610 mm ALUMINUM MANHOLE FRAME AND COVER
426	DROP SEWER CONNECTIONS
427	STUB OUT AND PLUGS
428	MANHOLE STEPS
429	INDUSTRIAL WASTE CONTROL VAULT WITH MANHOLE
440	SEWER BUILDING CONNECTION
441	SEWER CLEANOUT

DETAIL NO.



**STANDARD DETAIL  
METRIC**

**INDEX**

DETAIL NO.

**500 SERIES**  
**IRRIGATION AND STORM DRAIN INFORMATION**

501-1 HEADWALL  
501-2 HEADWALL  
501-3 HEADWALL – 1100 mm TO 2100 mm PIPE  
501-4 HEADWALL IRRIGATION 450 mm TO 1500 mm PIPE  
501-5 HEADWALL – DROP INLET  
502-1 TRASH RACK  
502-2 TRASH RACK  
503 IRRIGATION STANDPIPE  
504 CONCRETE BLOCK JUNCTION BOX  
505 CONCRETE PIPE COLLAR  
506 IRRIGATION VALVE INSTALLATION  
507 ENCASED CONCRETE PIPE (FOR SHALLOW INSTALLATION)  
510 CORRUGATED METAL PIPE AND INSTALLATION  
520 STORM DRAIN MANHOLE BASES (1200 mm OR SMALLER)  
521 STORM DRAIN MANHOLE BASES (1275 mm OR LARGER)  
522 STORM DRAIN MANHOLE SHAFT  
523-1 PRESSURE MANHOLE  
523-2 PRESSURE MANHOLE  
524 STORM DRAIN LATERAL PIPE CONNECTIONS  
530 1070 mm CURB OPENING CATCH BASIN – TYPE 'A'  
531 1680 mm CURB OPENING CATCH BASIN – TYPE 'B'  
532 2440 mm CURB OPENING CATCH BASIN – TYPE 'C'  
533-1 CATCH BASIN TYPE 'D'  
533-2 2130 mm OPENING CATCH BASIN – TYPE 'D' WITH LOCAL DEPRESSION  
533-3 2130 mm OPENING CATCH BASIN – TYPE 'D' WITH LOCAL DEPRESSION  
533-4 2130 mm OPENING CATCH BASIN – TYPE 'D' GRATE DETAILS  
534-1 CATCH BASIN – TYPE 'E'  
534-2 CATCH BASIN – TYPE 'E' (DETAILS)  
534-3 CATCH BASIN – TYPE 'E' (DETAILS)  
534-4 CATCH BASIN – TYPE 'E' (DETAILS)  
534-5 ALTERNATE GRATE STYLES – SUMP LOCATION  
535 CATCH BASIN – TYPE 'F' – FOR USE WITHOUT CURB  
536-1 COMMON DETAILS AND SECTIONS FOR CURB OPENING CATCH BASINS  
536-2 ALTERNATE COVER FOR CURB OPENING CATCH BASINS  
537 CATCH BASIN – TYPE 'G'  
538 CATCH BASIN – TYPE 'H'  
540-1 CATCH BASIN GRATES  
540-2 CATCH BASIN GRATES  
545 END SECTION – REINFORCED CONCRETE PIPE  
550 SPILLWAY INLET AND OUTLET  
552 CONCRETE CUT-OFF WALLS  
555 EROSION PROTECTION/RIPRAP

DETAIL NO.



**STANDARD DETAIL  
METRIC**

**INDEX**

DETAIL NO.

1. THESE DETAILS HAVE BEEN PREPARED IN AN EFFORT TO STANDARDIZE THE CONSTRUCTION DETAILS USED BY VARIOUS CONTRACTING AGENCIES IN MARICOPA COUNTY. THEY ARE TO BE USED IN CONJUNCTION WITH THE CURRENT METRIC EDITION OF THE "UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION" SPONSORED AND DISTRIBUTED BY THE MARICOPA ASSOCIATION OF GOVERNMENTS.
2. MANY NOTES WITHIN THESE DETAILS REFER TO VARIOUS SECTIONS OF THE "UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION." WHERE THIS REFERENCE IS MADE, ONLY THE ABBREVIATION "SECT." IS USED. AN EXAMPLE OF THIS REFERENCE WOULD BE: "CLASS 'A' CONCRETE PER SECT. 725."
3. MANY NOTES WITHIN THESE DETAILS REFER TO OTHER DETAILS WITHIN THIS BOOK. WHERE THIS REFERENCE IS MADE, THE ABBREVIATION "DETAIL" IS USED. AN EXAMPLE OF THIS WOULD BE: "SEE DETAIL 391 FOR VALVE BOX INSTALLATION."
4. MANY DETAILS COVER MORE THAN ONE SHEET. THESE SHEETS HAVE BEEN GIVEN THE SAME NUMBER WITH A SUFFIX NUMBER, EXAMPLE: 391-1 AND 391-2.
5. AN EFFORT HAS BEEN MADE TO INCLUDE THE MOST COMMONLY USED CONSTRUCTION DETAILS IN THIS BOOK. ITEMS WHICH REQUIRE DESIGN CONSIDERATION BY THE DESIGNING ENGINEER HAVE NOT BEEN INCULDED.
6. SOME OF THE DETAILS PRINTED HEREIN MAY BE USED BY OTHERS. THE DESIGNING ENGINEER SHOULD THEREFORE CONTACT THE AGENCY WITHIN WHOSE JURISDICTION HE IS WORKING FOR DIRECTION AS TO WHICH DETAIL OR PORTIONS OF DETAILS SHOULD BE USED.
7. DETAIL DRAWINGS ARE NOT TO SCALE.
8. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

DETAIL NO.

**101**



**STANDARD DETAIL  
METRIC**

**GENERAL INFORMATION**










































REVISED

**3-02-2000**

DETAIL NO.

**101**



CONCRETE PVMT. SECTION		MANHOLE		SINGLE CURB	
SUBGRADE SEAL SECTION		SEWER CLEANOUT		MAIL BOX	
SELECT MATERIAL SECTION		RAILROAD		EXISTING WATER LINE	
AGGREGATE BASE SECTION		IRRIGATION LINE		EXISTING TELEPHONE LINE	
BITUMINOUS PVMT. SECTION		IRRIGATION STANDPIPE		EXISTING SEWER LINE	
EXISTING PAVEMENT		"L" HEADWALL		EXISTING GAS LINE	
OBLITERATE PAVEMENT		TELEPHONE OR TEL. LINE		EXISTING STORM DRAIN LINE	
CONCRETE PAVEMENT		POWER OR JOINT LINE		EXISTING IRRIGATION LINE	
BITUMINOUS PAVEMENT		DOWN GUY & ANCHOR			
		STREET LIGHT			
SECTION LINE		STREET SIGN			
ROADWAY CENTER LINE		TRAFFIC SIGN			
SURVEY MONUMENT		TRAFFIC SIGNAL LIGHT			
FIRE HYDRANT		SIDEWALK			
WATER METER		CURB & GUTTER			
WATER OR GAS VALVE		VALLEY GUTTER			
GAS METER		SINGLE GUTTER			

DETAIL NO.

110



**STANDARD DETAIL  
METRIC**


## PLAN SYMBOLS

REVISED

3-02-2000

DETAIL NO.

110



DIMENSION SHOULD BE GIVEN ONCE ON EACH SHEET AND SHOULD BE PLACED NEAR THE CENTER OF THE SHEET. IF ANY OF THE GIVEN CONDITIONS CHANGE, THEY SHOULD BE REDIMENSIONED AT THE POINT OF CHANGE.

GIVEN DIMENSIONS IN ORDER STARTING WITH THE LONGEST AND ENDING WITH THE SHORTEST, AS SHOWN IN THE SKETCH.

GIVE COMPLETE DIMENSIONS.

IF THE CENTERLINE OF PAVEMENT DOES NOT FALL ON THE SECTION LINE OR MONUMENT LINE OF THE STREET, DIMENSION AS ABOVE AND SHOW THE DIFFERENCE BETWEEN THE SECTION OR MONUMENT LINE AND THE CENTERLINE.

DETAIL NO.

112



**STANDARD DETAIL  
METRIC**

**DIMENSIONING  
FOR ROAD IMPROVEMENT PLANS**


REVISED

3-03-2000

DETAIL NO.



112





### NOTES:

1. TYPE 'D' NORMALLY USED AT STREET INTERSECTIONS, AS SUBDIVISION MONUMENTS AND 1/16 CORNERS.
2. TYPE 'E' NORMALLY USED ON SECTION CORNERS, 1/4 CORNERS AND AT THE CENTER OF SECTIONS. CONCRETE POST IS CHAMFERED 20 mm AT TOP. MINIMUM LENGTH OF POST 800 mm, LENGTH DEPENDS ON SUBSURFACE OBSTRUCTIONS SUCH AS OLD CONCRETE PAVING, ROCK, ETC... 20 mm GALVANIZED PIPE SET IN THIS POST SHALL BE A MINIMUM OF 750 mm LONG EXCLUSIVE OF COUPLING, SEE PLANS.
3. CAP TO BE CONSTRUCTED OF RED BRASS OR BRONZE,
4. FRAME AND COVER TO INCLUDE CHAIN PER STD. DETAIL 270.



DETAIL NO.

120-2



STANDARD DETAIL  
METRIC


SURVEY MARKER  
(FOR UNINCORPORATED AREAS OF COUNTY)

REVISED


01-03-2002

DETAIL NO.


120-2




**TYPE "A"**



SEE NOTE 3



**TYPE "B"**



### NOTES:

1. FASTEN WITH M12x125 mm LAG SCREWS WITH 2 FLAT WASHERS OR (2) M16 BOLTS, WITH 4 FLAT WASHERS.
2. 38x184 mm DOUGLAS FIR PLANK (LENGTH TO BE DETERMINED ON PLANS.)
3. WHEN BARRICADE (TYPE "A") IS CONSTRUCTED ON BASES INSTEAD OF POSTS SET INTO THE GROUND, IT MAY BE DESIRABLE TO BALLAST THE BASES WITH SAND BAGS OR BY STAKING TO PROVIDE RESISTANCE TO OVERTURNING DURING PERIODS OF HIGH WINDS.
4. TWO COATS OF WHITE PAINT PER SECTION 790 SHALL BE APPLIED TO ALL EXPOSED SURFACES OF THE BARRICADE. AN ADDITIONAL, TWO COATS OF ORANGE PAINT PER SECTION 790 SHALL BE APPLIED TO CREATE THE ALTERNATE ORANGE AND WHITE STRIPES. HIGHWAY SAFETY SPHERES (BEADS) PER ADOT 708-2.02 SHALL BE APPLIED BY HAND TO ALL CROSS MEMBERS, FRONT AND BACK AND ON BOTH COLORS, IMMEDIATELY AFTER PAINTING. THE STRIPES SHALL SLOPE DOWNWARD IN THE DIRECTION TRAFFIC IS TO PASS.

DETAIL NO.

**130**



**MARICOPA  
ASSOCIATION of  
GOVERNMENTS**

**STANDARD DETAIL  
METRIC**

**BARRICADES**

REVISED

**04-19-2000**

DETAIL NO.

**130**

FLANGED STEEL 'U'  
CHANNEL (3.0 kg OR  
4.5 kg PER METER  
AS SPECIFIED)

65 mm DIA. STANDARD  
PIPE GALVANIZED OR  
73 mm O.D. STANDARD  
PIPE GALVANIZED  
(AS SPECIFIED)

50 mm DIA.  
STANDARD PIPE  
GALVANIZED

## NOTES


### TYPE 'A'

USE DRIVING HEAD FOR DRIVING ALL  
FLANGED STEEL 'U' CHANNEL POSTS.


IN LIEU OF DRIVING FLANGED STEEL  
'U' CHANNEL POSTS MAY BE SET IN  
CONCRETE BASE FOUNDATION AS  
PER TYPE 'B' BASE.

### TYPE 'B' & TYPE 'C'


CONCRETE BASE FOUNDATIONS SHALL  
BE CLASS 'C' CONCRETE AS PER SECT.  
505 AND 725.



TYPE 'A'



TYPE 'B'



TYPE 'C'

DETAIL NO.

131



STANDARD DETAIL  
METRIC

STREET SIGN BASE

REVISED


3-03-2000

DETAIL NO.


131

## NOTES

1. POSTS AND BLOCKS SHALL BE 200 mm x 200 mm ROUGH WOOD, PRESSURE TREATED AND UNPAINTED. HOLES SHALL BE BORED BEFORE TREATMENT. SEE SECT. 415
2. ALL GUARD RAIL PLATE, FITTINGS, HARDWARE, ETC. SHALL BE GALVANIZED.
3. TYPE 'A' GUARD RAIL INSTALLED ON NORMAL SHOULDER LINE.
4. TYPE 'B' GUARD RAIL INSTALLED ON WIDENED ROADWAY SHOULDER LINE.
5. TYPE 'B' INSTALLATION SHOWN. TYPE 'A' INSTALLATION SAME EXCEPT THAT INSIDE FACE OF GUARD RAIL SHALL FALL ON THE NORMAL SHOULDER LINE AS INDICATED BY PLAN DRAWING.




**ELEVATION**




**PLAN**

NOTE: LAP PLATES WITH EXPOSED EDGES AWAY FROM APPROACHING TRAFFIC



**SIDE ELEVATION**



**DETAIL NO. 1**

DETAIL NO.

**135-1**



**STANDARD DETAIL  
METRIC**


**STEEL GUARD RAIL**

REVISED


**3-03-2000**

DETAIL NO.

**135-1**



'W' SECTION BACK-UP PLATE  
FOR STEEL POSTS



'W' BEAM (STEEL POST)

DETAIL NO.

135-2



STANDARD DETAIL  
METRIC

STEEL GUARD RAIL


REVISED

3-03-2000

DETAIL NO.

135-2







**STANDARD FLARED  
TERMINAL SECTION**

**NOTES:**


1. TOP AND RUB RAIL SHALL NOT PROJECT MORE THAN 25 mm. IF ADJUSTMENT SHORTENING IS REQUIRED, THREADS SHALL BE LEFT IN FUNCTIONAL CONDITION.
2. HORIZONTAL DISTANCE BETWEEN TOP RAIL AND MEDIAN CURB SHALL NOT EXCEED 300 mm.



**DETAIL NO. 2 – MEDIAN BARRIER**



**INSTALLATION OF GUARD RAIL  
IN EMBANKMENT CURB SECTION**



**DETAIL NO. 3 – RUB RAIL SPLICE  
(SPLICE AT POSTS ONLY)**

DETAIL NO.

**135-3**



**STANDARD DETAIL  
METRIC**


**STEEL GUARD RAIL**

REVISED

**3-03-2000**

DETAIL NO.


**135-3**




### NOTE

1. 16 mm BOLT SIZE SELF DRILLING ANCHOR SHALL HAVE A MINIMUM 6.7 kN PULL OUT STRENGTH IN 20 MPa CONCRETE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.


## DETAIL NO. 4 ATTACHMENT OF GUARD RAIL TO STRUCTURES



25 mm SQUARE OR HEX. HEAD MACH. BOLT, NUT AND WASHERS



## DETAIL NO. 1 – GUARD RAIL POST INSTALLATION ON STRUCTURES



## DETAIL NO. 5 BUFFER END SECTION

DETAIL NO.  
**135-4**




**STANDARD DETAIL  
METRIC**

**STEEL GUARD RAIL**


REVISED  
**3-03-2000**

DETAIL NO.  
**135-4**






**TYPE A**




**TYPE B-1, B-2, AND B-3**



**TYPICAL SECTION**

**NOTE:**

1. DIMENSIONAL AND REINFORCEMENT CHANGES WILL BE PERMITTED UPON PRIOR WRITTEN APPROVAL OF THE ENGINEER.



**SAFETY CURB  
INSTALLATION ON DIRT**

DETAIL NO.

**150**



**STANDARD DETAIL  
METRIC**

**PRECAST SAFETY CURB**

REVISED

**3-03-2000**

DETAIL NO.



**150**

## NOTES

1. ALL CONCRETE SHALL BE CLASS 'C' PER SECT. 725.
2. FITTINGS NOT SPECIFICALLY DETAILED SHALL BE HEAVY DUTY DESIGN.
3. STRAIN POSTS SHALL BE SPACED AT 150 m MAXIMUM SPACING.
4. BOTH CORNER AND STRAIN POSTS SHALL HAVE STRAIN PANELS.
5. ALL POSTS SHALL BE CAPPED.
6. MEMBER SIZES SHALL BE THE FOLLOWING:

MEMBER	AISC SIZE	OUTSIDE DIA.
CORNER POST	65	73.03
LINE POST	40	48.26
STRAIN POST	40	48.26
BRACE	32	42.16
STRETCH BAR	4.76 x 19 FLAT	4.76 x 19 FLAT
GATE POST	90	101.60
TOP RAIL	32	42.16

7. CONSTRUCTION AND MATERIALS SHALL CONFORM TO SECT. 420 AND 722, RESPECTIVELY. SEE USS TABLE 722 FOR WEIGHTS OF MEMBERS.



DETAIL NO.

160



**STANDARD DETAIL  
METRIC**

**1830 mm CHAIN LINK  
FENCE AND GATE**

REVISED


3-03-2000

DETAIL NO.

160

**NOTE:**

L-xxx NUMBERS DESIGNATES FAA SPECIFICATION NO.



DETAIL NO.

170



STANDARD DETAIL  
METRIC


TYPICAL RUNWAY OR TAXIWAY  
EDGE LIGHTING DETAIL

REVISED

3-03-2000

DETAIL NO.

170



$$D = \frac{(100 - R)d + 0.9 RS \times 1000}{100}$$

WHERE:

D= DRY DENSITY OF SAMPLE CONTAINING R PERCENT ROCK, kg/m<sup>3</sup>.

R= PERCENT ROCK RETAINED ON 4.75 mm SIEVE.

d= DRY DENSITY OF PORTION PASSING 4.75 mm SIEVE, kg/m<sup>3</sup>.

S= BULK SP. GR. OF ROCK.

### EXAMPLE:

KNOWN: DRY DENSITY OF MATERIAL PASSING 4.75 mm SIEVE = 1826 kg/m<sup>3</sup>. PLOT AT A.

KNOWN: SPECIFIC GRAVITY OF ROCK = 2.5, PLOT AT B. DRAW LINE AB.

KNOWN: PERCENT OF ROCK IN TOTAL SAMPLE = 29. PLOT AT C. DRAW LINE CD AND LOCATE D AT INTERSECTION WITH AB. DRAW LINE DE LOCATING POINT E AT 1949. 1949 = DRY DENSITY IN kg/m<sup>3</sup> OF TOTAL SAMPLE CONTAINING 29% ROCK.

DETAIL NO.

190



STANDARD DETAIL  
METRIC


## ROCK CORRECTION PROCEDURE FOR MAXIMUM DENSITY DETERMINATION

REVISED

3-03-2000

DETAIL NO.

190



DETAIL NO.

200



STANDARD DETAIL  
METRIC

BACKFILL, PAVEMENT  
AND SURFACE REPLACEMENT


REVISED

01-03-2002



DETAIL NO.

200





$d$  = DESIGN THICKNESS OF A.C.  
PAVEMENT PLUS AGGREGATE BASE.



DETAIL NO.  
**201**




**STANDARD DETAIL  
METRIC**


**PAVEMENT SECTION AT TERMINATION**

REVISED  
**3-03-2000**


DETAIL NO.  
**201**



**PAVED ALLEY DETAIL**



**UNPAVED ALLEY DETAIL**



**RESIDENTIAL ALLEY DETAIL**

DETAIL NO.

202



MARICOPA  
ASSOCIATION of  
GOVERNMENTS

STANDARD DETAIL  
METRIC

ALLEY DETAILS (PAVED AND UNPAVED)


REVISED

3-03-2000

DETAIL NO.


202

M10 FLATHEAD STAINLESS STEEL  
CAP SCREW COUNTERSINK  
(6 EACH MIN.)




## NOTES:


1. ANGLE EQUALS 45° UNLESS SPECIFIED ON PLAN.
2. DIMENSION 'B' EQUALS 'A' + 600 mm.
3. ( ————— ) INDICATES DIRECTION OF FLOW.
4. PAINT STEEL ACCORDING TO SECTION 790.  
PAINT NUMBER 1-A OR 1-B.
5. R EQUALS 25 mm UNLESS OTHERWISE DIRECTED.
6. H EQUALS CURB FACE HEIGHT.
7. FOR ROLL CURB AND GUTTER, USE 600 mm  
TRANSITIONS TO VERTICAL CURB.



## DETAIL C



## SECTION 'A-A'



## SECTION 'B-B'

DETAIL NO.

203



STANDARD DETAIL  
METRIC


SCUPPERS

REVISED

3-03-2000

DETAIL NO.


203




**PLAN OF CONCRETE EQUIPMENT CROSSING**

**NOTES:**


1. WHEN EQUIPMENT CROSSING LIES ADJACENT TO BRIDGE OR BOX CULVERT, CONSTRUCT THE EQUIPMENT CROSSING TO WIDTH OF BRIDGE ROADWAY.
2. ALL DOWELS IN CENTER JOINTS SHALL BE DEFORMED BARS AND SHALL HAVE UNBROKEN BOND. THEY SHALL BE HELD SECURELY IN PLACE, PARALLEL TO THE SUBGRADE AND PERPENDICULAR TO THE CENTER LINE OF THE ROAD.
3. THE EDGING TOOL USED FOR ALL LONGITUDINAL JOINTS SHALL BE SO CONSTRUCTED AS TO PROVIDE A SMOOTH TROWELED SURFACE 75 mm WIDE ON EACH SIDE OF THE JOINT.
4. IF APPROVED BY THE ENGINEER, OTHER DEFORMATIONS MAY BE USED IN LONGITUDINAL JOINT - DETAIL 'C'.
5. DETAIL 'C' TO BE USED ONLY WHEN FULL WIDTH CAN NOT BE POURED IN ONE POUR. USE DETAIL 'D' IF FULL WIDTH IS POURED IN ONE POUR.




**SECTION A-A**




**SECTION B-B**




**LONGITUDINAL JOINT DETAIL 'C'**



**LONGITUDINAL JOINT DETAIL 'D'**



**JOINT AT NEW BRIDGE DETAIL 'F'**



**JOINT AT EXISTING BRIDGE DETAIL 'E'**

DETAIL NO.

**204**



**STANDARD DETAIL  
METRIC**


**EQUIPMENT CROSSING**

REVISED

**3-03-2000**


DETAIL NO.

**204**



## NOTES:

1. W - INDICATES WIDTH OF PAVED SURFACE OF TURNOUT.  
L - INDICATES LENGTH OF PAVED SURFACE OF TURNOUT.  
R - RADIUS.
2. SIZE AND TYPE OF TURNOUT SHALL BE NOTED ON PLANS AS FOLLOWS:  
90° - NO RADUIS: WxL-SURFACE-TYPE; (4 x 9 m-A.C.-TYPE "B" TURNOUT).  
90° - WITH A RADIUS: WxLxR-SURFACE-TYPE; (4 x 9 x 4.5 m-A.C.-TYPE "C" TURNOUT). OTHER THAN 90° WITH 2 RADII-TYPE "S": WxLxR<sub>1</sub>xR<sub>2</sub>-SURFACE-TYPE; (4 x 9 x 4.5 x 15 m-A.C.-TYPE "S" TURNOUT).  
OR IT MAY BE NOTED ON PLANS IN CONVENTIONAL TERMS.
3. TURNOUTS TO BE STRAIGHT TYPE UNLESS OTHERWISE NOTED ON PLANS.
4. A.C. AND BASE MATERIAL THICKNESS FOR TURNOUTS SHALL BE THE SAME AS SHOWN ON THE ROADWAY SECTION, UNLESS OTHERWISE NOTED.
5. ANY EXCAVATION OR EMBANKMENT FOR TURNOUTS IS INCLUDED IN THE ROADWAY QUANTITIES.
6. TURNOUTS ARE TO BE PLACED WHERE SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.



**TYPICAL VALLEY GUTTER TURNOUT**



**TYPICAL STRAIGHT TURNOUT**

\* UNLESS OTHERWISE NOTED ON PLANS

DETAIL NO.

**205**



**STANDARD DETAIL  
METRIC**


**PAVED TURNOUTS**

REVISED


**3-03-2000**

DETAIL NO.

**205**




ANCHOR BAR  
WELDED TO  
ANGLE



ANGLE  
102x76x12.7

SEE DETAIL  
ABOVE



**SECTION D-D**

**NOTES:**

1. TRANSITION TO SPILLWAY/CHANNEL AS PER APPROVED PLANS.
2. A CENTER WALL SHALL BE INSTALLED IN SCUPPERS WIDER THAN 1200 mm OR IF MORE THAN 1 SCUPPER IS BUILT IN SERIES.
3. EXPANSION JOINT FILLER SHALL BE 13 mm BITUMINOUS TYPE PREFORMED EXPANSION JOINT FILLER, A.S.T.M. D-1751.

DETAIL NO.

**206-2**



MARICOPA  
ASSOCIATION of  
GOVERNMENTS

**STANDARD DETAIL  
METRIC**

**CONCRETE SCUPPER**


REVISED

**3-03-2000**


DETAIL NO.

**206-2**


VERTICAL CURB AND GUTTER  
(TYPE A)



RIBBON CURB  
(TYPE B)




ROLL CURB AND GUTTER  
(TYPE C)



(TYPE D)

SPECIAL SECT. USE FOR HIGH  
SIDE CURB WITH SHEET DRAINAGE  
ACROSS STREET / PA



- NOTES:

1. ALL EXPOSED SURFACES TO BE TROWEL FINISHED EXCEPT AS SHOWN. SEE SECT. 340.
2. H=150 OR AS SPECIFIED ON PLANS.
3. CONTRACTION JOINT SPACING 3.0 m MAXIMUM.
4. EXPANSION JOINTS AS PER SECT. 340.

NOTES:



1. CONSTRUCT CURB AND INSTALL 13 mm MASTIC EXPANSION JOINTS, A.S.T.M. D-1751. SECT. 340.
2. BROOM FINISH ALL SURFACES.
3. RIBBON CURB MAY SLOPE TOWARDS PAVEMENT OR PARKWAY AS INDICATED ON PLANS.
4. CONTRACTION JOINT SPACING 3.0 m MAXIMUM.

NOTES:

1. ALL WORK AND MATERIALS SHALL CONFORM TO SECT. 340, 505 AND 725. BROOM FINISH EXPOSED SURFACE.
2. CONTRACTION JOINT SPACING 3.0 m MAXIMUM.
3. EXPANSION JOINTS AS PER SECT. 340.




## CURB AND GUTTER TRANSITION




NOTES:

1. THE CURB TRANSITION WILL BE PAID FOR AS TYPE 'C'. WHEN A PROJECT CONSISTS OF TYPE 'C' CURB AND GUTTER THROUGHOUT, THE ENTIRE RETURN SHALL BE MEASURED AND PAID FOR AS TYPE 'A'.
2. WHERE PROPOSED CONSTRUCTION IS TO BE CONNECTED TO EXISTING CURB AND GUTTER, THE TRANSITION SHALL BE INDICATED ON PLANS.

CURB WARNING BEACON




INTEGRAL ROLL CURB,  
GUTTER AND SIDEWALK



NOTES:


1. CONCRETE TO BE MONOLITHIC POUR. EXPOSED SURFACE FINISH AS PER SIDEWALK AND GUTTER DETAIL.
2. CONTRACTION JOINT SPACING 5.0 m MAXIMUM.
3. EXPANSION JOINTS PER SECT. 340.




TYPE 'A'

**NOTES:**

1. ALL VERTICAL SURFACES TO BE FORMED.
2. VERTICAL SURFACES DOWN FROM 50 mm BELOW UNDISTURBED SOIL MAY BE PLACED AGAINST NEAT CUT IF APPROVED BY THE ENGINEER AND CONCRETE WILL NOT EXTEND MORE THAN 25 mm BEYOND THEORETICAL FACE.
3. ALL EXPOSED SURFACES TO BE STRIPPED GREEN AND TROWEL FINISHED.
4. CONCRETE CURBS CONFORM TO SECT. 340.
5. MAXIMUM SPACING OF CONTRACTION JOINTS IS 3 m.
6. CONCRETE TO BE CLASS 'B' PER SECT. 725.



TYPICAL CURB TERMINATION



TYPE 'B'

DETAIL NO.

222



STANDARD DETAIL  
METRIC


SINGLE CURB -  
TYPES A, B AND TERMINATION

REVISED

01-03-2002

DETAIL NO.

222



**NOTE:**

LENGTH OF TRANSITION SHALL BE EQUAL TO RADIUS OF MEDIAN NOSE, (1500 mm MINIMUM). FOR LOCATION SEE PLANS.

DETAIL NO.

**223**



**STANDARD DETAIL  
METRIC**







**MEDIAN NOSE TRANSITION**

REVISED

**3-03-2000**

DETAIL NO.

**223**



**DRAINAGE INLET**

**MANHOLE COVERS**

**MANHOLE COVERS**

DETAIL NO.

**224**



**MARICOPA  
ASSOCIATION of  
GOVERNMENTS**

**STANDARD DETAIL  
METRIC**




**JOINT FOR DRAINAGE INLETS  
AND MANHOLE COVERS**

REVISED

**3-03-2000**

DETAIL NO.

**224**



DETAIL NO.

230



STANDARD DETAIL  
METRIC


SIDEWALKS

REVISED

3-03-2000


DETAIL NO.

230




## NOTES:

1. CONTROL ELEVATIONS SHOWN ARE IN RELATION TO THE GUTTER AND ARE LOCATED RADially. GUTTER ELEVATION=0.
2. CLASS 'B' CONCRETE CONSTRUCTION AS PER SECTION 725.
3. WHEN CURB HEIGHTS OF 175 mm ARE SHOWN ON PLANS, USE DIMENSIONS SHOWN IN [ ]'S.



SECTION B-B



SECTION A-A

## CONTROL ELEVATIONS

DETAIL NO.

231



**STANDARD DETAIL  
METRIC**


**SIDEWALK RAMPS - TYPE 'A'**

REVISED

3-03-2000


DETAIL NO.

231




## NOTES:


1. CONTROL ELEVATIONS SHOWN ARE IN RELATION TO THE GUTTER AND ARE LOCATED RADially. GUTTER ELEVATION=0.
2. CLASS 'B' CONCRETE CONSTRUCTION AS PER SECT. 725.
3. WHEN CURB HEIGHTS OF 175 MM ARE SHOWN ON PLANS, USE DIMENSIONS SHOWN IN [ ]'S.



## CONTROL ELEVATIONS



## SECTION B-B



## SECTION A-A

DETAIL NO.

232



STANDARD DETAIL  
METRIC


SIDEWALK RAMPS - TYPE 'B'

REVISED

3-06-2000

DETAIL NO.

232



DETAIL NO.

233



**STANDARD DETAIL  
METRIC**

**SIDEWALK RAMPS - TYPE 'C'**




REVISED

3-06-2000

DETAIL NO.

233





DETAIL NO.

234



STANDARD DETAIL  
METRIC


SIDEWALK RAMPS - TYPE 'D'

REVISED

01-03-2002


DETAIL NO.

234





- NOTES:**
1. ALL CONCRETE TO BE CLASS 'A' UNLESS OTHERWISE APPROVED. (SECT. 725).
  2. 1200 mm ON PROJECTS UNDER THE JURISDICTION OF THE COUNTY ENGINEER AND THE CITY OF MESA.
  3. EITHER CONSTRUCTION JOINT OR CONTRACTION JOINT IS REQUIRED AT CENTERLINE OF STREET.
  4. A SEPARATE CONCRETE PAD IS REQUIRED WHEN VALLEY GUTTER IS POURED HALF AT A TIME.

**SECTION A-A**  
**VALLEY GUTTER**



## NOTES:

1. DEPRESSED CURB SHALL BE PAID FOR AT THE UNIT PRICE BID FOR THE TYPE OF CURB USED AT THAT LOCATION.
2. WHEN WIDTH EXCEEDS 6.7 m PROVIDE A CONTRACTION JOINT ON D/W CENTERLINE.
3. BACK OF D/W OR FACE OF FUTURE S/W.
4. MASTIC EXPANSION JOINT THROUGH CURB AND GUTTER. EXPANSION JOINT FILLER SHALL BE 13 mm BITUMINOUS TYPE PREFORMED EXPANSION JOINT FILLER A.S.T.M. D-1751.
5. BACK OF CURB – CONSTRUCTION JOINT OR SCORE MARK.
6. CLASS 'B' CONCRETE, SECT. 725.
7. SUBGRADE PREPARATION, SECT. 301.
8. FLOW LINE OF GUTTER.
9. DEPRESSED CURB.
10. SECT. A-A AND ELEVATION, D/W VERTICAL CURB AND GUTTER OR ROLL TYPE CURB AND GUTTER.
11. ROLL TYPE CURB AND GUTTER NOT PERMITTED IN THE CITY OF MESA
12. 5 mm GROOVES AT 25 mm O.C. FULL WIDTH OF 1500 mm WARP SECTION, EACH SIDE OF DRIVEWAY. SEE DETAIL NO. 1 ON TYPE 'D' RAMP DETAIL NO. 234.



## COMMERCIAL AND INDUSTRIAL

DRIVEWAY WIDTH	MIN.	MAX.	CLASS	DEPTH <sup>x</sup>
COMMERCIAL	*5.0 m	12.0 m	B	150 mm
INDUSTRIAL	*5.0 m	12.0 m	B	150 mm
*7.5 m MIN. FOR TWO WAY TRAFFIC				

## RESIDENTIAL

DRIVEWAY WIDTH	MIN.	MAX.	CLASS	DEPTH <sup>x</sup>
MAJOR STREET	5.0 m	9.0 m	B	125 mm
COLLECTOR STREET	*4.0 m	9.0 m	B	125 mm
LOCAL STREET	4.0 m	9.0 m	B	125 mm
*5.0 m DESIRABLE				

DETAIL NO.

250



**STANDARD DETAIL  
METRIC**

**DRIVEWAY ENTRANCES**

REVISED

3-06-2000

DETAIL NO.

250





TABLE A		
ZONING	DRIVEWAY WIDTH	
	MIN.*	MAX.
COMMERCIAL	5.0 m	12.0 m
INDUSTRIAL	5.0 m	12.0 m
* 7.5 m WHERE 2-WAY TRAFFIC IS ANTICIPATED		

TABLE B		
ZONING	DRIVEWAY WIDTH	
	MIN.*	MAX.
RESIDENTIAL	5.0 m	9.0 m
MAJOR STREET	5.0 m	9.0 m
COLLECTOR STREET	4.0 m	9.0 m
LOCAL STREET	4.0 m	9.0 m
* 5.0 m WIDTH IS DESIRABLE		

### NOTES:

- EXPANSION JOINT FILLER SHALL BE 13 mm BITUMINOUS TYPE PREFORMED EXPANSION JOINT FILLER, A.S.T.M. D-1751.
- THIS TYPE D/W TO BE USED ONLY UPON APPROVAL OF ENGINEER.



### SECTION A-A

DETAIL NO.

251



**STANDARD DETAIL  
METRIC**

**RETURN TYPE DRIVEWAYS**

REVISED




3-06-2000

DETAIL NO.


251

## NOTES: (PARKING BAY)

1. SUFFICIENT RIGHT-OF-WAY MUST BE AVAILABLE TO CONSTRUCT PARKING BAY.
2. PARKING BAYS WILL NOT BE ALLOWED WHERE THEY CONFLICT WITH BUS STOPS.




## PARKING BAY



## NOTES: (BUS BAY)

1. SUFFICIENT RIGHT-OF-WAY MUST BE AVAILABLE TO CONSTRUCT BUS BAY.
2. RADII, SIDEWALK, CURB AND GUTTER, PAVING SLOPE AND CONCRETE APRON SHALL BE CONSTRUCTED AS FOR PARKING BAYS.



## BUS BAY

DETAIL NO.

252



STANDARD DETAIL  
METRIC


BUS AND PARKING BAYS

REVISED

3-06-2000


DETAIL NO.

252




### NOTES:

1. EXPANSION JOINT FILLER SHALL BE 13 mm BITUMINOUS TYPE PREFORMED EXPANSION JOINT FILLER A.S.T.M. D-1751. BETWEEN SIDEWALK AND ALLEY ENTRANCE AND THROUGH CURB AND GUTTER.
2. CLASS 'B' CONCRETE, PER SECT. 725.
3. SUBGRADE PREPARATION, PER SECT. 301.
4. 5mm GROOVES AT 25 mm O.C. FULL WIDTH OF 1500 mm WARP SECTION, EACH SIDE OF ALLEY ENTRANCE. SEE DETAIL NO. 1 ON TYPE 'D' RAMP DETAIL NO. 234.



**ELEVATION**



**SECTION A-A**

DETAIL NO.

**260**



**STANDARD DETAIL  
METRIC**



**ALLEY ENTRANCE  
(WITH COMBINED CURB AND GUTTER)**

REVISED

**3-06-2000**

DETAIL NO.


**260**



**ELEVATION**

**NOTE:**

5 mm GROOVES AT 25 mm O.C. FULL WIDTH OF 1200 mm WARP SECTION, EACH SIDE OF ALLEY ENTRANCE. SEE DETAIL NO. 1 ON TYPE 'D' RAMP DETAIL 234.



**SECTION A-A**

DETAIL NO.

**261**



**STANDARD DETAIL  
METRIC**

**ALLEY ENTRANCE  
(WITH ROLL TYPE CURB AND GUTTER)**

REVISED



**3-06-2000**

DETAIL NO.


**261**







ELEVATION



SECTION A-A

DETAIL NO.

263



**STANDARD DETAIL  
METRIC**


**WING TYPE ALLEY ENTRANCE  
(WITH ROLL TYPE CURB AND GUTTER)**

REVISED


3-06-2000

DETAIL NO.


263





## WATER VALVE, SURVEY MONUMENT, OR SEWER CLEAN OUT FRAME AND GRADE ADJUSTMENT



LETTERS ON COVER TO BE AS FOLLOWS:  
"SEWER", "WATER", OR "SURVEY" AS DIRECTED  
TOTAL WIDTH OF WORD "SEWER" OR "WATER"  
95 mm. TOTAL WIDTH OF WORD "SURVEY"  
114 mm. LETTER SIZE 16x19 mm, RAISED 2 mm  
ABOVE LEVEL OF COVER, TYPE OF LETTERS  
TO BE SUBMITTED FOR APPROVAL.



DETAIL TYPICAL FOR BOTH FRAME AND COVER



DETAIL NO.

270



STANDARD DETAIL  
METRIC


FRAME AND COVER INSTALLATION  
AND GRADE ADJUSTMENT

REVISED

01-03-2002

DETAIL NO.


270






CLASS 'C' CONCRETE AS PER SECT. 725  
FORM AS REQUIRED TO KEEP CLEAR OF JOINTS.

**NOTE:**

THIS DETAIL COVERS WATER GATE VALVES, 100 mm TO 300 mm INCLUSIVE, REGARDLESS OF TYPE OF PIPE USED. LARGER LINES TO BE DETAILED ON PLANS.



**WATER GATE VALVE**



**BUTTERFLY VALVE**

**NOTES:**

1. THIS DETAIL COVERS BUTTERFLY VALVE INSTALLATION, 75 mm TO 300 mm INCLUSIVE, REGARDLESS OF TYPE OF PIPE OR JOINT USED. LARGER LINES TO BE DETAILED ON PLANS.
2. VALVE BOX AND COVER REQUIRED PER DETAILS 270 AND 391.

DETAIL NO.

301



STANDARD DETAIL  
METRIC


BLOCKING FOR  
WATER GATE AND BUTTERFLY VALVES

REVISED


3-06-2000

DETAIL NO.

301




**DEAD ENDS**




**HORIZONTAL BENDS**


LRN = SHORTEST LENGTH  
OF PIPE RESTRAINED TO  
THE RUN OF THE TEE  
FITTING (BOTH SIDES OF TEE).



**TEES**



**VERTICAL DOWN BENDS**



**VERTICAL UP BEND**

RESTRAINED LENGTHS, LR, FOR DUCTILE IRON PIPE												
NOMINAL PIPE SIZE (mm)	HORIZONTAL BENDS			TEES		VERTICAL OFFSETS						DEAD ENDS
						90° BEND FITTINGS		45° BEND FITTINGS		22 1/2° BEND FITTINGS		
	90°	45°	22°	LRN=0 m	LRN=3 m	DOWN BEND	UP BEND	DOWN BEND	UP BEND	DOWN BEND	UP BEND	
100	5.5	2.1	1.2	9.1	2.4	9.4	5.5	4.0	2.1	1.8	0.9	9.4
150	7.6	3.0	1.5	13.1	6.1	13.4	7.6	5.5	3.0	2.7	1.5	13.4
200	9.8	4.0	1.8	17.1	10.4	17.7	9.8	7.3	4.0	3.4	1.8	17.7
250	11.6	4.9	2.4	20.7	13.7	21.0	11.6	8.8	4.9	4.3	2.4	21.0
300	13.7	5.8	2.7	24.4	17.4	24.7	13.7	10.4	5.8	4.9	2.7	24.7
350	15.5	6.4	3.0	27.7	20.7	28.0	15.5	11.6	6.4	5.5	3.0	28.0
400	17.4	7.3	3.4	31.4	24.1	31.7	17.4	13.1	7.3	6.4	3.4	31.7
450	18.9	7.9	3.7	34.4	27.4	35.1	18.9	14.6	7.9	7.0	3.7	35.1
500	20.7	8.5	4.3	38.1	30.5	38.4	20.7	15.8	8.5	7.6	4.3	38.4
600	24.1	10.0	4.9	44.2	36.9	44.8	24.1	18.6	10.1	8.8	4.9	44.8

RESTRAINED LENGTHS, LR, FOR DUCTILE IRON PIPE WITH POLYETHYLENE WRAP												
NOMINAL PIPE SIZE (mm)	HORIZONTAL BENDS			TEES		VERTICAL OFFSETS						DEAD ENDS
						90° BEND FITTINGS		45° BEND FITTINGS		22 1/2° BEND FITTINGS		
	90°	45°	22°	LRN=0 m	LRN=3 m	DOWN BEND	UP BEND	DOWN BEND	UP BEND	DOWN BEND	UP BEND	
	100	7.9	3.4	1.5	21.0	5.5	21.9	7.9	9.1	3.4	4.3	
150	11.0	4.6	2.1	30.2	14.3	31.1	11.0	12.8	4.6	6.1	2.1	31.1
200	14.3	5.8	2.7	39.6	23.8	40.5	14.3	16.7	5.8	7.9	2.7	40.5
250	17.1	7.0	3.4	47.9	31.4	48.5	17.1	20.1	7.0	9.8	3.4	48.5
300	19.8	8.2	4.0	56.4	39.9	57.0	19.8	23.5	8.2	11.3	4.0	57.0
350	22.6	9.4	4.6	64.3	47.5	65.2	22.6	27.1	9.4	12.8	4.6	65.2
400	25.0	10.4	4.9	72.5	55.8	73.5	25.0	30.5	10.4	14.6	4.9	73.5
450	27.4	11.3	5.5	80.2	63.1	81.1	27.4	33.5	11.6	16.2	5.5	81.1
500	29.9	12.5	6.1	88.1	71.0	89.0	29.9	36.9	12.5	17.7	6.1	89.0
600	34.4	14.3	6.7	102.7	85.3	103.6	34.4	43.0	14.3	20.7	6.7	103.6

**NOTES:**

1. ALL JOINTS WITHIN THE SPECIFIED LENGTH LR MUST BE RESTRAINED.  
ALL LENGTHS ARE GIVEN IN METERS.
2. THE MAXIMUM TEST PRESSURE SHALL NOT EXCEED 1.38 MPa
3. THE MINIMUM DEPTH OF BURY SHALL BE 900 mm TO TOP OF PIPE.
4. RESTRAINED LENGTHS MAY BE REDUCED WHEN SUPPORTED BY ENGINEERING CALCULATIONS.

DETAIL NO.

**303-2**



STANDARD DETAIL  
METRIC





**JOINT RESTRAINT FOR DUCTILE IRON AND  
POLYETHYLENE WRAPPED DUCTILE IRON WATER PIPES**



REVISED

3-06-2000


DETAIL NO.

**303-2**






SECTION A-A




SECTION B-B

**NOTE:**


FOR CASTING SPECIFICATIONS  
SEE SECT. 787.



TOP OF COVER



SLOT DETAIL



DETAIL NO.

311



STANDARD DETAIL  
METRIC



CAST IRON WATER METER BOX  
COVER NO. 2

REVISED

3-06-2000

DETAIL NO.


311





**SECTION A-A**

**NOTES:**

1. INSPECTION PLATE IS SAME AS USED WITH METER BOX COVER NO. 4.
2. FOR CASTING SPECIFICATIONS, SEE SECTION 787.



**DETAIL  
TOP OF COVER & PLATE**



**LETTERING DETAIL**

DETAIL NO.

**312**



**STANDARD DETAIL  
METRIC**

**CAST IRON WATER METER BOX  
COVER NO. 3**




REVISED

**3-06-2000**

DETAIL NO.

**312**





DETAIL NO.

313



**STANDARD DETAIL  
METRIC**


**CAST IRON WATER METER BOX  
COVER NO. 4**

REVISED

3-06-2000

DETAIL NO.

313



PLAN VIEW

SECTION A-A

**NOTES:**

1. THE METER BOXES SHALL CONFORM TO THE DIMENSIONS AS SHOWN AND SHALL BE MADE OF PORTLAND CEMENT CONCRETE POURED AND TAMPED (OR VIBRATED) IN TRUE FORMS.
2. USE CLASS 'AA' CONCRETE PER SECT. 725.

METER BOX DIMENSIONS				
DIMS	BOX NUMBER			
	1	2	3	4
A	482	622	749	851
B	305	426	470	578
C	279	305	330	305
D	356	482	603	705
E	406	560	673	775
F	228	337	381	502
G	178	286	324	432
H	228	362	394	502
I	152	213	235	289
J	38	44	44	38
K	19	28	25	25
L	6	9	9	9
M	406	534	648	775
N	64	89	102	102
	16 mm OR 19 mm METER	25 mm METER	38 mm METER	50 mm METER

SECTION B-B

DETAIL NO.

320



**STANDARD DETAIL  
METRIC**


**CONCRETE WATER METER BOXES**

REVISED


3-06-2000

DETAIL NO.

320





### PRE-CAST VAULT SECTION



### CAST-IN-PLACE VAULT SECTION

NOTE: PRECAST REINFORCED VAULT SECTIONS SHALL BE CONSTRUCTED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND DETAILS AS APPROVED BY ENGINEER.



DETAIL NO.

321



STANDARD DETAIL  
METRIC


STANDARD WATER METER VAULT

REVISED

3-06-2000

DETAIL NO.


321



**PLAN**

CONCRETE: CLASS 'B' PER SECT. 725  
NORMALLY, CURE 24 HOURS BEFORE  
BACKFILLING.

OPTIONAL BLOCKING – 50x200x300 mm  
SOLID CONCRETE MASONRY UNITS  
AS INDICATED.



**ELEVATION**

**NOTES:**

1. TAPPING SLEEVE TO BE PLACED A MINIMUM OF 450 mm FROM ANY BELL COUPLING, VALVE, FITTING OR OTHER OBSTRUCTION
2. CONTRACTOR SHALL EXCAVATE AS SHOWN AND SHALL SET TAPPING SLEEVE AND VALVE AND TIGHTEN ALL BOLTS PRIOR TO THE PRESSURE TEST.
3. ALL TAPPING SLEEVES AND VALVES MUST BE PRESSURE TESTED PRIOR TO BLOCKING OR TAPPING. THE TEST MUST BE WITNESSED AND APPROVED BY THE INSPECTOR.
4. BLOCKS ARE TO EXTEND TO UNDISTURBED GROUND AND BE INSTALLED BEFORE THE TAP IS MADE. ALL FLANGE BOLTS SHALL BE FREE AND CLEAR OF CONCRETE.
5. TAPS SHALL BE MADE BY CITY CREWS AT PREVAILING RATES OR BY APPROVED CONTRACTORS WHEN ALLOWED BY CITY.
6. THIS DETAIL COVERS TAPPING SLEEVES 100 mm THROUGH 400 mm IN SIZE ON DUCTILE IRON, CAST IRON AND ASBESTOS CEMENT PIPE. ANY OTHER SIZE OR TYPE OF PIPE WILL REQUIRE A SEPARATE SUBMITTAL AND APPROVAL BY THE ENGINEER.

SIZE OF PIPE BEING CONNECTED (mm)	MINIMUM THRUST AREA REQUIRED EQUALS (AxB) (m <sup>2</sup> )
100 AND LESS	0.28
150	0.37
200	0.56
250	0.84
300	1.21
400	2.14

DETAIL NO.

**340**



**STANDARD DETAIL  
METRIC**


**INSTALLING TAPPING  
SLEEVES AND VALVES**

REVISED

**3-06-2000**

DETAIL NO.

**340**



DETAIL NO.

342



STANDARD DETAIL  
METRIC


# CONCRETE PRESSURE PIPE TAPPING SLEEVE

REVISED

3-06-2000

DETAIL NO.

342



# SECTION A-A

DETAIL NO.

345-1



STANDARD DETAIL  
METRIC

75 mm, 100 mm, 150 mm  
WATER METER


REVISED

3-06-2000

DETAIL NO.

345-1

FOR VAULT CONSTRUCTION  
SEE DETAIL 321



## LEGEND

- ① DOUBLE STRAP ALL BRONZE SERVICE SADDLES.
- ② CORP. STOP, 50 mm (BALL TYPE).
- ③ ADAPTER, FLANGED, TO MECH. JOINT FOR A.C.P.
- ④ GATE VALVE, FLANGED, WITH HAND WHEEL, OPEN LEFT.
- ⑤ TURBOMETER: ROCKWELL SERIES 'W' OR HERSEY SERIES 'M.H.R.' OR NEPTUNE TRIDENT TURBINE.
- ⑥ FLANGED SWING CHECK VALVE WITH EXTERNAL LEVER AND WEIGHT.
- ⑦ 50 mm BRONZE CHECK VALVE.
- ⑧ 50 mm TURBOMETER: ROCKWELL 'W-160' OR HERSEY 'M.H.R.' OR NEPTUNE TRIDENT TURBINE.
- ⑨ STRAINER (75 mm, 100 mm, 150 mm) AVAILABLE FROM METER MANUFACTURER, INSTALL ONLY WHEN 'TURBO' IS USED.
- ⑩ FLANGED SPOOL (3 PIPE DIAMETERS IN LENGTH).
- ⑪ O.S.&Y. GATE VALVE, FLANGED WITH HAND WHEEL OPEN LEFT, AND RISING STEM.
- ⑫ TURBOMETER U.L. APPROVED: ROCKWELL W-5000 DR. OR W-2000 DR. OR HERSEY FM.-CT. OR NEPTUNE TURBINE-FS-UL.
- ⑬ 150 mm OR 250 mm STRAINER, U.L. APPROVED.
- ⑭ 50 mm THREADED OUTLET AND GATE VALVE.

## NOTES

1. FOR LARGER METERS, SPECIAL VAULT DESIGN IS REQUIRED.
2. USE OF REMOTE READING DEVICE AT OPTION OF UTILITIY.
3. CERTAIN AGENCIES AND/OR UTILITIES PREFER TO CONSTRUCT VAULT, CONTACT AGENCY INVOLVED PRIOR TO VAULT CONSTRUCTION.

DETAIL NO.

345-2



**STANDARD DETAIL  
METRIC**


**100 mm, 150 mm WATER METER  
WITH ON-SITE FIRE HYDRANTS**

REVISED

3-06-2000

DETAIL NO.



345-2



### NOTES:

1. FIRELINE FROM CITY MAIN TO PROPERTY LINE SHALL BE CONSTRUCTED OF CAST IRON PIPE.
2. REINFORCING TO BE 15M REBAR ON 230 mm CENTERS EACH WAY ON TOP AND 460 mm CENTERS EACH WAY ON THE SIDES.
3. COVERS TO CONSIST OF TWO METER BOX COVERS DET. 314.
4. BY-PASS METER TO BE ACCORDING TO GOVERNING AGENCY.
5. CHECK VALVE TO BE GLOBE MODEL "A" GRINNELL, HERSEY MODEL D.C., VIKING MODEL "A", OR APPROVED EQUAL.
6. VAULT SHALL BE CONSTRUCTED IN OWNERS PROPERTY AGAINST THE FRONT PROPERTY LINE OR ANOTHER APPROVED LOCATION. WALLS AND FENCES SHALL NOT OBSTRUCT ACCESS.
7. CITY CONTROL VALVE TO BE REQUIRED AT MAIN.
8. PARTS OF PIPE TO BE EMBEDDED IN CONC. SHALL BE WRAPPED WITH 1470 g/m<sup>2</sup> ASPHALT ROOFING FELT.
9. REMOTE READING DEVICE SHALL BE OF SELF GENERATING ELECTRICAL TYPE. HYDRAULIC OR MECHANICAL DRIVE REGISTERS WILL NOT BE ACCEPTABLE.
10. CONCRETE TO BE CLASS 'B' PER SECT. 725.

DIA. OF PIPE (mm)	X (mm)	Y (mm)	Z (mm)	BY-PASS METER SIZE (mm)	A (mm)
100	1550	1700	1250	16x19	750
150	1700	1850	1250	16x19	750
200	1850	1850	1500	25	900
250	2000	1850	1750	38	900



DETAIL NO.

346



STANDARD DETAIL  
METRIC

FIRE LINE DETECTOR CHECK VAULT

REVISED

3-06-2000




DETAIL NO.

346



## NOTES:

1. JOINTS BETWEEN THE VALVE AND THE MAIN SHALL BE FLANGED TYPE. JOINTS BETWEEN THE VALVE AND HYDRANT SHALL BE RESTRAINT OR MECHANICAL TYPE.
2. 90° BEND NOT REQUIRED IF SUFFICIENT ROOM FOR PERPENDICULAR INSTALLATION.
3. FOR CONCRETE THRUST BLOCKS, SEE DETAIL 380.
4. A FLANGE JOINT BY MECHANICAL JOINT VALVE MAY BE USED AS THE TRANSITION BETWEEN THE JOINT TYPES.
5. SEE DETAIL 362 FOR LOCATION OF HYDRANT.
6. FINISH GRADE SHALL BE GROUND LEVEL, SIDEWALK, ADJACENT SIDEWALK, PAVEMENT, ADJACENT CURB OR OTHER NEARBY OBSTRUCTION DENYING WRENCH ACCESS TO THE BOTTOM FLANGE BOLTS.



DETAIL NO.

360



STANDARD DETAIL  
METRIC

FIRE HYDRANT INSTALLATION

REVISED


3-06-2000

DETAIL NO.


360

## NOTES:

1. OBSTRUCTIONS SUCH AS UTILITY POLES, STREET SIGNS, IRRIGATION BOXES, FENCES, ETC., MUST NOT BE PLACED BETWEEN CURB AND HYDRANT AND WITHIN THE RADIUS FOR FIRE DEPT. ACCESS.
2. DIMENSIONS SHOWN ON CONSTRUCTION DRAWINGS SUPERSEDE LOCATIONS SHOWN HERE.
3. ON LOCATIONS IN MIDBLOCK, THE FIRE HYDRANT WILL BE ALIGNED WITH A PROPERTY LINE.



PARKWAY AREA OR NO SIDEWALK



AREA WITH SIDEWALK

DETAIL NO.

362



STANDARD DETAIL  
METRIC


## LOCATIONS FOR NEW FIRE HYDRANTS

REVISED


3-06-2000

DETAIL NO.


362



### CAST IRON



### CAST IRON MECHANICAL JOINT



### ASBESTOS CEMENT

### NOTES:

1. THIS DETAIL COVERS MOVING OF WATER MAINS 50 mm TO 300 mm ONLY.
2. THRUST BLOCKING AS PER DET. 380 & 381.
3. IF OFFSET IS TO GO OVER OBSTRUCTION, JOINT RESTRAINTS MUST BE USED.
4. PIPE IS TO BE CAST IRON OR DUCTILE IRON.

DETAIL NO.

370



**STANDARD DETAIL  
METRIC**

**VERTICAL REALIGNMENT OF WATER MAINS**








REVISED

3-06-2000

DETAIL NO.

370


## TYPICAL LOCATIONS OF THRUST BLOCKS



### NOTES:

1. TABLE IS BASED ON 1370 kPa TEST PRESSURE AND 145 kPa SOIL. IF CONDITIONS ARE FOUND TO INDICATE SOIL BEARING IS LESS, THE AREAS SHALL BE INCREASED ACCORDINGLY.
2. AREAS FOR PIPES LARGER THAN 400 mm SHALL BE CALCULATED FOR EACH PROJECT.
3. FORM ALL NON-BEARING VERTICAL SURFACES.
4. THRUST BLOCKS ARE TO EXTEND TO UNDISTURBED GROUND. CONCRETE TO BE CLASS 'C', SECT. 725.

PIPE SIZE (mm)	WATER PIPE	
	TEE, DEAD END, 90° BEND	45° & 22 1/2° BENDS
100 OR LESS	0.28	0.28
150	0.37	0.28
200	0.56	0.28
250	0.93	0.46
300	1.30	0.65
400	2.23	1.11



SECTION A-A

DETAIL NO.

380



STANDARD DETAIL  
METRIC

THRUST BLOCKS FOR WATER LINES

REVISED

3-06-2000


DETAIL NO.

380



ENLARGED  
'A'


FRAME AND  
COVER PER  
DETAIL 270



TYPE 'A'

**NOTES:**

1. CURB STOP TO BE MUELLER ORISEAL (H-10283), FORD BALL VALVE B11-777, HAYES BULLETIN 400, J. JONES (J-1900) OR APPROVED EQUAL.
2. REDUCER MAY BE USED WHEN CONNECTING TO SMALLER GALVANIZED PIPE.
3. THIS DETAIL IS TO BE USED WHEN CONNECTING EXISTING GALVANIZED PIPE TO ASBESTOS CEMENT PIPE OR CAST IRON PIPE.



TYPE 'B'

**NOTE:**

1. VALVE BOX TO BE SUPPORTED ON BRICKS TO PREVENT VERTICAL LOADS FROM BEING TRANSMITTED TO THE SMALL PIPE.

DETAIL NO.

**389**



**STANDARD DETAIL  
METRIC**


**CURB STOP WITH VALVE BOX  
AND COVER**

REVISED


**3-07-2000**

DETAIL NO.

**389**



TYPE 'A'



TYPE 'B'

VALVE BOX LOCATION MAY VARY IF  
APPROVED BY THE CITY ENGINEER.

DETAIL NO.

**390**



**STANDARD DETAIL  
METRIC**


**CURB STOP WITH FLUSHING PIPE**

REVISED


**3-07-2000**

DETAIL NO.

**390**




**TYPE 'C'**




**VIEW A-A**

**NOTES:**

1. VALVE BOX SHALL BE ADJUSTED TO THE FINISHED GRADE PRIOR TO PLACING OF THE ASPHALTIC CONCRETE SURFACE.
2. USE PARKSON TYLER, APCO OR EQUAL DEEP SKIRTED LID (100 mm OR MORE) TYPE, SLIDING ADJUSTABLE CAST IRON VALVE BOX C.I. MIN. T.S. 207 MPa.
3. GROUND BELOW CONCRETE PAD OR 3 BRICKS TO BE COMPACTED 95% OF MAX. DENSITY.



**TYPE 'A'**  
(TO BE USED IN AREAS SUBJECT TO VEHICULAR TRAFFIC.)



**TYPE 'B'**  
(NOT SUBJECT TO VEHICULAR TRAFFIC)

DETAIL NO.

**391-1**



**STANDARD DETAIL  
METRIC**

**VALVE BOX INSTALLATION  
AND GRADE ADJUSTMENT**



REVISED

**3-07-2000**

DETAIL NO.

**391-1**





### NOTES:

1. EXTENSION STEM: WITH SQUARE SOCKET ON BOTTOM TO FIT 51 mm SQUARE VALVE NUT. EXTENSION TO VALVE STEMS REQUIRED ON ALL VALVES INSTALLED WHERE OPERATING NUT IS OVER 1500 mm BELOW SURFACE. LENGTH TO FIT EACH INSTALLATION. OPERATING NUT TO BE HELD ON TOP OF EXTENSION WITH STOP NUT.
2. IF TWO OR MORE JOINTS OF A.C.P. ARE USED TO MAKE RISER, USE STANDARD A.C. PIPE RUBBER GASKET COUPLING TO JOIN PIPE. WHERE RISER LENGTH EXCEEDS 3000 mm USE 300 mm A.C. PIPE.
3. STEM PAINTING: ALL STEEL TO HAVE PRIME COAT OF PAINT NO. 1-D AND ONE HEAVY APPLICATION (FINISH COAT) OF PAINT NO. 9 AS PER SECT. 790.

DETAIL NO.

391-2



**STANDARD DETAIL  
METRIC**

## VALVE BOX INSTALLATION


REVISED

3-07-2000


DETAIL NO.

391-2


VALVE BOX AND COVER  
FOR DETAIL 391-1,  
TYPE A



VALVE BOX AND COVER  
FOR DETAIL 391-1,  
TYPE B



VALVE BOX AND COVER  
FOR DETAIL 391-1,  
TYPE C



## NOTES:

1. THE DEBRIS CAP SHALL BE DESIGNED AND INSTALLED TO PREVENT DEBRIS SUCH AS DIRT, DUST SAND, ETC., FROM PASSING AROUND THE CAP AND DOWN INTO THE VALVE HOUSING. THE CAP SHALL BE HELD IN PLACE BY A MECHANISM WHICH WILL NOT DAMAGE THE VALVE HOUSING. ONCE INSTALLED THE CAP MUST WITHSTAND, WITHOUT SLIPAGE, A MINIMUM VERTICAL FORCE OF 225 NEWTONS, AT A LOADING RATE OF 25 mm/MINUTE.
2. THE CAP SHALL BE MANUFACTURED OF CORROSIVE RESISTANT MATERIALS.
3. DEBRIS CAP SHALL BE INSTALLED AS CLOSE UNDER THE CAST IRON COVER WITHOUT INTERFERING WITH COVER OPERATION.
4. THE CAP SHALL BE CAPABLE OF SECURELY HOLDING A STANDARD LOCATING COIL, "SCOTCH MARK" 4 DISK MARKER BY 3M OR EQUAL.
5. THE CAP SHALL BE CONSTRUCTED TO ALLOW THE DEVICE TO BE SECURED BY A LOCK. THE LOCK (PAD, BARREL, ETC.) SHALL BE SUPPLIED BY THE AGENCY.
6. THE HANDLE AND/OR BODY OF THE CAP SHALL BE INTEGRALLY COLORED IF REQUIRED BY THE AGENCY. IF REQUIRED, THE COLOR SHALL CONFORM TO THE ONE CALL LOCATING SERVICE (BLUE STAKE) COLORS (ARS 40-360.21).
7. THE CAP SHALL BE INSTALLED IN ALL VALVE HOUSINGS AS REQUIRED BY THE CONTRACT DOCUMENTS OR BY THE AGENCY'S POLICIES.
8. THE DEBRIS CAP SHALL BE MANUFACTURED BY SW SERVICES, INC. PHOENIX, ARIZONA OR EQUAL.

DETAIL NO.

392



STANDARD DETAIL  
METRIC



DEBRIS CAP INSTALLATION

REVISED

3-07-2000

DETAIL NO.

392



**SECTION A-A**

**NOTES:**

1. LAY PIPE TO LINE AND GRADE ON BRICK CRADLE.
2. PLACE CLASS 'C' CONCRETE PER SECT. 725 & 505, IN SUCH A MANNER AS NOT TO FLOAT THE PIPE.

DETAIL NO.

**402**



**STANDARD DETAIL  
METRIC**



**ENCASED PIPE FOR CANAL CROSSINGS**

REVISED


**3-07-2000**

DETAIL NO.


**402**



**TYPE 'A'**



**SECTION B-B**



**TYPE 'B'**

**NOTES:**

1. TYPE 'A' PIPE SUPPORT MAY BE USED FOR ANY TYPE CROSSING CONDITION.
2. TYPE 'C' PIPE SUPPORT MAY BE USED FOR CROSSING PIPES WITH A BELL DIAMETER OF 450 mm OR LESS IF SUFFICIENT CLEARANCE OVER STORM SEWER IS AVAILABLE AND TOTAL SPAN IS LESS THAN 10.5 m.
3. INTERMEDIATE PIPE SUPPORT SHALL BE USED IN CONJUNCTION WITH TYPE 'C' PIPE SUPPORT IF TOTAL SPAN EXCEEDS MAX. 'W' IN TABLE.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL SUPPORTS BOTH PERMANENT AND TEMPORARY. TEMPORARY SUPPORTS SHALL NOT BE A SEPARATE PAY ITEM.
5. PERMANENT PIPE SUPPORTS MAY BE DECREASED FROM PLAN QUANTITIES OR EXTENDED TO INCLUDE SOME LISTED BELOW AS TEMPORARY SUPPORTS IF CONDITIONS WARRANT THESE CHANGES AT THE TIME OF CONSTRUCTION. DECISION SHALL BE MADE BY THE ENGINEER.
6. WHEN TYPE 'A' PIPE SUPPORT IS USED AND WHENEVER SO DIRECTED BY THE ENGINEER, THE CONTRACTOR SHALL PIERCE THE WALL WITH SUITABLE OPENINGS TO PREVENT UNEQUAL PRESSURE RESULTING FROM FLOODING OF THE BACKFILL. THE VOLUME OF THE PIERCED OPENING SHALL NOT EXCEED 1/2 THE VOLUME OF THE SUPPORTING WALL.
7. USE TYPE 'B' PIPE SUPPORT INSTEAD OF TYPE 'C' WHEN CLEARANCE IS LESS THAN 'Y' IN TABLE, BETWEEN PIPES.

**SCHEDULE OF REQUIRED SUPPORTS**

PERMANENT	TEMPORARY	
SEWER LINES	CAST IRON PIPE	CONC. BOX CULVERT
	CONC. IRRIG. PIPE	TRAFFIC CONTROL CONDUIT
	BURIED TELCO.	WATER & SEWER LINES
	GAS PIPES	
	CONC. STORM DRAIN	

**NOTE**

OTHER UTILITIES AS NOTED ON THE PLANS OR AS REQUIRED BY THE ENGINEER AT TIME OF CONSTRUCTION.

DETAIL NO.

403-1



**STANDARD DETAIL  
METRIC**

**PIPE SUPPORT ACROSS TRENCHES**

REVISED


3-07-2000

DETAIL NO.


403-1

TABLE


'W'	DEPTH OF COVER ON SUPPORTS (mm)			
	0 mm TO 2500 mm		2500 mm TO 5000 mm	
	BAR NO.	Y(mm)	BAR NO.	Y(mm)
TO 1800	15M	200	20M	275
2100	15M	225	20M	300
2400	15M	250	20M	325
2700	20M	275	20M	350
3000	20M	300	25M	375
3300	20M	325	25M	400
3700	20M	350	25M	425
4000	25M	375	25M	475
4300	25M	400	25M	500
4600	25M	425	25M	525
4900	25M	450		
5200	25M	475		




TYPE 'C'




SECTION D-D



SECTION A-A



INTERMEDIATE SUPPORT FOR TYPE 'B' CROSSINGS



PLAN FOR TYPE 'B' SUPPORT

DETAIL NO.

403-2



STANDARD DETAIL  
METRIC


PIPE SUPPORT ACROSS TRENCHES

REVISED

3-07-2000

DETAIL NO.

403-2



DETAIL NO.  
**403-3**



**STANDARD DETAIL  
METRIC**




**ALTERNATE TO PIPE SUPPORT**


REVISED  
**3-07-2000**

DETAIL NO.  
**403-3**


## NOTES:

1. SEPARATION DISTANCES AND/OR OTHER EXTRA PROTECTION SHALL BE REQUIRED TO PROTECT WATER MAINS FROM CONTAMINATION BY SANITARY SEWER MAINS.
2. THIS CRITERIA APPLIES TO PARALLEL MAINS AS WELL AS CROSSINGS.
3. SEE CROSS SECTION DETAIL FOR LIMITS OF SEPARATION/EXTRA PROTECTION. ALL DISTANCES ARE MEASURED PERPENDICULARLY FROM THE OUTSIDE OF THE PIPES.
  - A. NO WATER MAINS SHALL FALL WITHIN ZONE A.
  - B. EXTRA PROTECTION WILL BE REQUIRED WHEN THE WATER MAIN FALLS WITHIN ZONE B. EXTRA PROTECTION SHALL CONSIST OF CONSTRUCTING THE SANITARY SEWER MAIN WITH MECHANICAL JOINT OR RESTRAINED JOINT DUCTILE IRON PIPE FOR A DISTANCE OF TEN FEET ON EITHER SIDE OF THE WATER MAIN. THE DUCTILE IRON PIPE SHALL COMPLY WITH THE AGENCY'S REQUIREMENTS FOR SEWER INSTALLATION. IN THE CASE OF A CROSSING, THE NUMBER OF JOINTS SHALL BE HELD TO A MINIMUM WITH ONE FULL JOINT OF PIPE CENTERED OVER/UNDER THE OTHER. AN ALTERNATE PROTECTION MAY CONSIST OF ENCASEMENT BOTH PIPES IN CONCRETE AS SHOWN HEREIN.
  - C. NO ADDITIONAL PROTECTION WILL BE REQUIRED OUTSIDE OF THE ZONE A AND B.
4. SEPARATION REQUIREMENTS FOR 4" OR 6" INDIVIDUAL HOUSE SERVICE CONNECTIONS SHALL COMPLY WITH THE AGENCY'S PLUMBING CODES.
5. RECLAIMED WATER SHALL BE CONSIDERED AS POTABLE WATER WHEN PLACED NEXT TO A SANITARY SEWER AND CONSIDERED A PRESSURE OR FORCE SANITARY SEWER MAIN WHEN PLACED NEXT TO A POTABLE WATER MAIN.






**PLAN VIEW OF REPLACEMENT**




**REPLACEMENT WHEN NEW TRENCH  
600 mm WIDE OR LESS**

COMPACTION SHALL BE DONE IN ACCORDANCE WITH SECT. 601



**REPLACEMENT WHEN NEW TRENCH  
MORE THAN 600 mm WIDE**



**SECTION 'A-A'**

**NOTES:**

1. BROKEN PIPE SHALL BE REPLACED WITH A MINIMUM OF ONE FULL JOINT AND TWO SHORT LENGTHS WITH UNBROKEN BELLS. CONSTRUCTION AND JOINTS TO BE MADE AS PER SECTION 615.

DETAIL NO.

**405**



**STANDARD DETAIL  
METRIC**

**BROKEN SEWER LINE REPLACEMENT**

REVISED


**3-09-2000**

DETAIL NO.


**405**



FOR INSTALLATION  
IN P.V.M.T. SEE  
DETAIL 422




**TYPE 'B' TOP**



**NOTES:**



1. PRE-CAST, REINFORCED M.H. SECTIONS SHALL BE MANUFACTURED IN ACCORDANCE WITH A.S.T.M. C-478M EXCEPT AS MODIFIED BY DETAILS BELOW LEFT.
2. M.H. STEPS SHALL BE INSTALLED AT SITE OF M.H. SECTION MANUFACTURE MINIMUM CLEARANCE EACH SIDE OF M.H. LEG SHALL BE 25 mm. STEPS SHALL BE MOUNTED WITH 2 TO 1 SAND/CEMENT DRY PACK MORTAR (SEE DET. 428 FOR M.H. STEP.)
3. USE LOW ALKALI CEMENT ONLY.




**TYPE 'A' TOP**

(PRE-CAST ECCENTRIC CONICAL TOP M.H.)

ALTERNATE BASE \*\*  
WITH KNOCKOUTS FOR PIPES.  
CLEARANCE AROUND PIPES  
25 mm MIN. - 75 mm MAX.  
EXCEPT LOWER CORNERS



**ADJUSTING RING DETAIL**



DETAIL NO.

420



STANDARD DETAIL  
METRIC


PRE-CAST CONCRETE SEWER MANHOLE

REVISED


3-09-2000

DETAIL NO.

420




422




FOR COVER LETTERING  
SEE NOTE ON DETAIL 424


**FACE OF COVER**  
**CAST IRON**





**BACK OF COVER**



**CAST IRON**  
**MANHOLE RING**



**SECTION OF COVER**  
APPROX. WEIGHT 125 kg



**SECTION OF RING**  
APPROX. WEIGHT 95 kg

**NOTES:**

1. WEIGHT OF CASTING SHALL BE NO MORE THAN 2% LESS THAN THE APPROXIMATE WEIGHT SPECIFIED.
2. CASTINGS SHALL CONFORM TO SECT. 787.

DETAIL NO.

**423**



**STANDARD DETAIL**  
**METRIC**


**WATER TIGHT 760 mm**  
**MANHOLE FRAME AND COVER**

REVISED

**3-09-2000**

DETAIL NO.


**423**



**BOTTOM VIEW - TOP VIEW**


WT. (CL. 30) - 93 kg  
WT. (CL. 35) - 77 kg

**610 mm MANHOLE FRAME AND COVER**



**BOTTOM VIEW**


WT. (CL. 30) - 91 kg  
WT. (CL. 35) - 82 kg



**BOTTOM VIEW - TOP VIEW**


WT. (CL. 30) - 102 kg  
WT. (CL. 35) - 99 kg

**760 mm MANHOLE FRAME AND COVER**




**BOTTOM VIEW**


WT. (CL. 30) - 147 kg  
WT. (CL. 35) - 94 kg




**SECTION OF FRAME**



**SECTION 'A-A' OF COVER**



**SECTION OF FRAME**



**SECTION 'D-D' OF COVER**

**NOTE:**

LETTERING ON MANHOLE COVER TO CONTAIN NAME OF AGENCY AND UTILITY FOR WHICH MANHOLE IS NEEDED, (I.E. "PHOENIX SANITARY SEWER"), OR AS DIRECTED. THE TOTAL WIDTH OF INDIVIDUAL LETTERS TO BE SUCH THAT LETTERS AND WORDS ARE EQUALLY SPACED AND BALANCED TO FORM A COMPLETE CIRCLE WITH SPACERS BEFORE AND AFTER THE WORD IDENTIFYING THE AGENCY INVOLVED. LETTERS TO BE 51 mm IN HEIGHT AND RAISED 3 mm ABOVE LEVEL OF COVER. TYPE OF LETTERS TO BE SUBMITTED FOR APPROVAL. WEIGHT OF CASTINGS SHALL BE NO MORE THAN 2% LESS THAN THE APPROXIMATE WEIGHT SPECIFIED. CASTINGS SHALL CONFORM TO SECTION 787.

DETAIL NO.

**424**



**STANDARD DETAIL  
METRIC**




**610 mm AND 760 mm  
MANHOLE FRAME AND COVER**

REVISED



**3-09-2000**

DETAIL NO.

**424**



#### RIB DETAIL



MATERIAL SHALL CONFORM TO A.S.T.M. STANDARDS  
 B 179-65 ALLOY SN122A  
 B 179-65 ALLOY CN42A  
 B 108-65 ALLOY SC103A  
 (ALL 3 ACCEPTABLE)

LETTERING ON MANHOLE COVER TO CONTAIN NAME OF AGENCY AND UTILITY FOR WHICH MANHOLE IS NEEDED. (I.E. "PHOENIX SANITARY SEWER"), OR AS DIRECTED. THE TOTAL WIDTH OF INDIVIDUAL LETTERS TO BE SUCH THAT LETTERS AND WORDS ARE EQUALLY SPACED AND BALANCED TO FORM A COMPLETE CIRCLE WITH SPACERS BEFORE AND AFTER THE WORD IDENTIFYING THE AGENCY INVOLVED. LETTERS TO BE 51 mm RAISED 3 mm ABOVE LEVEL OF COVER. TYPE OF LETTERS TO BE SUBMITTED FOR APPROVAL. WEIGHT OF CASTINGS SHALL BE NO MORE THAN 2% LESS THAN THE APPROXIMATE WEIGHT SPECIFIED. CASTINGS SHALL CONFORM TO SECT. 787.

SHALL CONFORM TO SECT. 625.3.1 - (FRAME AND COVER).

DETAIL NO.

425



STANDARD DETAIL  
METRIC


610 mm ALUMINUM  
MANHOLE FRAME AND COVER

REVISED


3-09-2000

DETAIL NO.

425



**TYPE A**  
750 mm TO 1500 mm DROP



**TYPE B**  
1500 mm OR MORE

DETAIL NO.

426



**STANDARD DETAIL  
METRIC**


## DROP SEWER CONNECTIONS

REVISED


3-09-2000

DETAIL NO.

426




**TYPICAL STUB OUT**




**NOTES:**

1. NOTE: COMPACT SOIL AT END OF PIPE TO 95% OF MAXIMUM DENSITY.
2. IF DEPTH OF COVER IS LESS THAN 1500 mm OR GREATER THAN 3000 mm, INCREASE PLUG THICKNESS A MIN. OF 100 mm.



**SEWER LINE**



DETAIL NO.

**427**



**STANDARD DETAIL  
METRIC**

**STUB OUT AND PLUGS**



REVISED

**3-09-2000**

DETAIL NO.





**427**






1. ALL DIMENSIONS ARE MINIMUM EXCEPT WHERE NOTED.  
2. CASTING AS PER SECT. 787.

## CAST IRON MANHOLE STEP




1. STEPS SHALL BE PLACED INTO WET CONCRETE WALL DURING MANUFACTURE OR MORTARED INTO HOLES AFTER CONCRETE HAS SET.
2. POLYPROPYLENE MUST MEET REQUIREMENTS OF A.S.T.M. 2146, TYPE II, GRADE 16906.

## POLYPROPYLENE MANHOLE STEP




**PLAN VIEW**



**SECTION A-A**

MANHOLE FRAME AND  
COVER PER DET. NO. 423



**MANHOLE & COVER SLAB**

**NOTES:**

1. THIS CONTROL VAULT WITH MANHOLE AND COVER SHALL BE USED ON 150 mm AND 200 mm DIAMETER SEWER WITH FLOWS IN THE RANGE OF 2.5 L/s TO 21.5 L/s.
2. VAULT TO BE CONSTRUCTED ON STRAIGHT RUN OF BUILDING SEWER. ACCESSIBLE AND SAFELY LOCATED ON THE OWNERS PROPERTY ADJACENT TO A PUBLIC RIGHT-OF-WAY.
3. THE PALMER BOWLUS FLUME SHALL BE INSTALLED PER THE MANUFACTURERS RECOMMENDATIONS.
4. THE PRE-CAST CONCRETE VAULT SHALL BE RECTANGULAR WITH MINIMUM INSIDE DIMENSIONS OF 1220 mm WIDE AND 1830 mm LONG AND AT A DEPTH OF THE DESIGN OF THE BUILDING SEWER.
5. A SHOP DRAWING SHALL BE SUBMITTED TO THE CONTRACTING AGENCY FOR APPROVAL BEFORE INSTALLATION OF THE VAULT AND THE PALMER BOWLUS FLUME WILL BE ALLOWED.

DETAIL NO.

**429**



**STANDARD DETAIL  
METRIC**


**INDUSTRIAL WASTE CONTROL  
VAULT WITH MANHOLE**

REVISED


**3-09-2000**

DETAIL NO.

**429**



1. CONSTRUCTION DETAIL APPLIES WHERE CONTRACTOR BUILDS HOUSE CONNECTION. TAP EXTENDS TO PROPERTY LINE IN ALLEYS OR STREETS OR TO EASEMENT LINE.
2. SIZE OF TAP SHALL BE DESIGNATED ON PLANS.
3. DETAILS SHOWN MUST BE MET FOR MINIMUM CONDITION OF LESS THAN 1500 mm.
4. CONSTRUCT TAP AT MINIMUM SLOPE IF COVER WILL BE LESS THAN 1500 mm AT PROPERTY LINE.



5. IF DEPTH REQUIRES, MINIMUM SLOPE CAN BE REDUCED TO 1% PROVIDED STUB IS STAKED TO GRADE.
6. FOR DEEPER LATERAL OR TRUNK SEWER CONDITION, THE WYE AND 1/8 BEND OR THE TEE AND 1/16 BEND WILL BE ROTATED TOWARD THE VERTICAL POSITION AS REQUIRED TO OBTAIN 1500 mm COVER OVER TAP AT PROPERTY LINE OR EASEMENT LINE.
7. END OF TAP TO BE SEALED AND MARKED AS NOTED.

DETAIL NO.

**440**



**STANDARD DETAIL  
METRIC**


**SEWER BUILDING CONNECTIONS**

REVISED


**3-09-2000**

DETAIL NO.

**440**



CLEANOUT INSTALLATION



SEWER TAP AT CLEANOUT

DETAIL NO.

441



**STANDARD DETAIL  
METRIC**


**SEWER CLEANOUT**

REVISED



3-09-2000

DETAIL NO.


441




INVERT GRADE SET BY  
ENGINEER OR BY  
S.R.V.W.U.A. ENGINEERS  
IN THEIR LATERALS




## SECTION B-B



STRAIGHT TYPE



'L' TYPE PLAN



'U' TYPE

DETAIL NO.

501-1



STANDARD DETAIL  
METRIC


HEADWALL

REVISED


3-10-2000

DETAIL NO.

501-1



**DOUBLE PIPE HEADWALL**



**ELEVATION**


CONCRETE BLOCK HEADWALLS JOINED WITH CEMENT MORTAR AND CONCRETE PLASTERED BOTH SIDES OF WALL FULL HEIGHT AND SHALL BE CURED PER SECT. 726.

**NOTES:**

1. ALL CONCRETE SHALL BE CLASS 'A' PER SECT. 505 & 725.
2. CONCRETE BLOCK PER SECT. 510, 775 & 776.
3. CONCRETE REINF. SHALL BE 15M BAR, 300 mm BOTH WAYS.

HEADWALL DIMENSIONS					
*NOMINAL PIPE SIZE	L <sup>1</sup>	L <sup>2</sup>	L <sup>3</sup>	L <sup>4</sup>	L <sup>5</sup>
300	410	610	1120	250	860
375	610	810	1220	300	910
450	610	1020	1420	360	1020
525	810	1220	1630	380	1120
600	810	1220	1630	460	1190
750	810	1630	2030	560	1400
900	1020	2030	2440	560	1570
1050	1220	2440	2840	660	1750

\* NOMINAL PIPE SIZE GIVEN FOR REINFORCED CONC. PIPE.



PIPE SIZE	W
300-550 mm INCL.	280 mm
600-1100 mm INCL.	330 mm

**DETAIL "A"**

DETAIL NO.

**501-2**



**STANDARD DETAIL  
METRIC**


**HEADWALL**

REVISED


**3-10-2000**

DETAIL NO.


**501-2**




**INLET HEADWALL**



**OUTLET HEADWALL**




**INLET HEADWALL FACE ELEVATION  
OUTLET SIMILAR**




**SECTION B-B**

CONCRETE SHALL  
BE CLASS 'A' PER  
SECT. 725



**SECTION A-A**



**BEVEL DETAIL**

## 1:1 1/2 EMBANKMENT SLOPE

NOMINAL PIPE SIZE		D	TYPE	DIMENSIONS			CONC. (m <sup>3</sup> )		REINF. STEEL (kg)
R.C.P.	C.M.P.			F	E	X	C.M.P.	R.C.P.	
1050	1000	1070	1 (IN)	1570	1570	530	3.42	3.34	129
			2 (OUT)	1570	580	530	2.65	2.59	100
1200	1200	1220	3 (IN)	1730	1730	580	4.01	3.92	151
			4 (OUT)	1730	640	580	3.11	3.04	117
1350	1400	1370	5 (IN)	1830	1830	640	4.51	4.44	174
			6 (OUT)	1830	690	640	3.52	3.45	135
1500		1520	7 (IN)	2030	2030	690	—	5.17	199
			8 (OUT)	2030	740	690	—	3.99	154
1650		1680	9 (IN)	2180	2180	740	—	5.88	226
			10 (OUT)	2180	790	740	—	4.54	175
1800	1800	1830	11 (IN)	2340	2340	790	6.78	6.64	255
			12 (OUT)	2340	840	790	5.24	5.12	197
1950	2000	1980	13 (IN)	2490	2490	840	7.59	7.42	286
			14 (OUT)	2490	910	840	5.86	5.73	217
2100	2200	2130	15 (IN)	2640	2640	890	8.42	8.24	318
			16 (OUT)	2640	970	890	6.52	6.37	246

(IN) REFERS TO INLET  
(OUT) REFERS TO OUTLET

## 1:4 EMBANKMENT SLOPE

NOMINAL PIPE SIZE		D	TYPE	DIMENSIONS			CONC. (m <sup>3</sup> )		REINF. STEEL (kg)
R.C.P.	C.M.P.			F	E	X	C.M.P.	R.C.P.	
1050	1000	1070	17 (IN)	2640	2640	910	5.93	5.79	223
			18 (OUT)	2640	970	910	4.21	4.11	159
1200	1200	1220	19 (IN)	2640	2640	1070	6.38	6.23	240
			20 (OUT)	2640	970	1070	4.60	4.50	173
1350	1400	1370	21 (IN)	2640	2640	1220	6.82	6.67	258
			22 (OUT)	2640	970	1220	4.99	4.88	188
1500		1520	23 (IN)	2840	2840	1320	—	7.63	295
			24 (OUT)	2840	1040	1320	—	5.55	215
1650		1680	25 (IN)	2950	2950	1450	—	8.48	324
			26 (OUT)	2950	1070	1450	—	6.19	238
1800	1800	1830	27 (IN)	2950	2950	1600	9.13	8.93	344
			28 (OUT)	2950	1070	1600	6.78	6.64	255
1950	2000	1980	29 (IN)	3050	3050	1730	9.96	9.74	375
			30 (OUT)	3050	1120	1730	7.45	7.28	280
2100	2200	2130	31 (IN)	3250	3250	1830	11.14	10.89	420
			32 (OUT)	3250	1190	1830	8.27	8.09	312

DETAIL NO.

**501-3**



**STANDARD DETAIL  
METRIC**


**HEADWALL 1100 mm  
TO 2100 mm PIPE**

REVISED


**3-10-2000**

DETAIL NO.

**501-3**




**PLAN**




**SECTION A-A**

NOMINAL PIPE SIZE		PIPE I.D.	DIMENSIONS			CONC. (m <sup>3</sup> )		REINF. STEEL (kg)
R.C.P.	C.M.P.		L	E	F (APPROX)	R.C.P.	C.M.P.	
450	450	460	610	300	530	0.71	0.72	31
600	600	610	610	300	530	0.79	0.82	37
750	800	760	910	460	790	1.08	1.13	51
900	900	910	1220	610	1060	1.51	1.56	71
1050	1000	1070	1520	760	1320	1.98	2.04	96
1200	1200	1220	1830	910	1590	2.48	2.55	127
1350	1400	1370	2130	1070	1840	3.02	3.11	158
1500		1520	2440	1220	2110	3.61		193

2 - 20M BARS BEND TO CONFORM TO PIPE



**ELEVATION**



**SECTION B-B**

### NOTES:

1. ALL CONCRETE SHALL BE CLASS 'A' PER SECT. 725.
2. ALL REINFORCING BARS SHALL BE 15M EXCEPT 20M BARS OVER PIPE. BAR SPACING APPROXIMATELY 300 mm C TO C UNLESS OTHERWISE NOTED.
3. 30° WING WALL FLARE SHOWN; 45° NORMALLY DESIRABLE.

DETAIL NO.

**501-4**



**STANDARD DETAIL  
METRIC**

**HEADWALL IRRIGATION  
450 mm TO 1500 mm PIPE**


REVISED

**3-10-2000**


DETAIL NO.

**501-4**






**PLAN**



**SECTION Y-Y**


**NOTES:**

1. HIGH POINT OF HEADWALL SHALL NOT PROJECT MORE THAN 75 mm ABOVE SLOPE.
2. ALL CONCRETE SHALL BE CLASS 'A' PER SECT. 725.
3. ALL REINFORCING BARS SHALL BE 15M, 300 mm C TO C AND 75 mm CLEAR TO INSIDE OF FLOOR AND WALLS.



**ELEVATION**

ELEVATION  
PER PLAN



**SECTION Z-Z**

PIPE			DIMENSIONS							
NOMINAL PIPE SIZE		I.D.	W		A	B	E	F	J	K
R.C.P.	C.M.P.		SINGLE	DOUBLE						
450	450	460	760	1580	810	380	230	398	230	460
600	600	610	910	1980	1070	495	345	598	280	690
750	800	760	1070	2390	1320	610	460	785	330	910
900	900	910	1220	2800	1580	720	570	987	410	1140
1050	1000	1070	1370	3200	1830	835	685	1185	460	1370

DETAIL NO.

**501-5**



**STANDARD DETAIL  
METRIC**



**HEADWALL DROP INLET**

REVISED

**3-10-2000**

DETAIL NO.

**501-5**




### TRASH RACK

### POURED WALLS


15M REINFORCED BARS 450 mm O.C. BOTH WAYS, CLASS 'A' CONC PER SECT. 505, 725 & 727.

### BLOCK WALLS

BLOCK HEADWALL TO HAVE ONE 15M REINF. BAR CENTERED IN EACH CORE FOR FULL HEIGHT AND CORES FILLED WITH CONCRETE OR CEMENT GROUT (3:1 RATIO). ALL BLOCKS TO BE JOINTED WITH MORTAR. PLASTERED ON EXPOSED SURFACES THEN SPRAY WITH WHITE PIGMENTED CURING COMPOUND. SECT. 510, 727 & 776.




### RACK BARS



### 45° BLOCK CORNER

### NOTES:

1. REMOVE ALL SCALE FROM RACK BARS. METAL SPRAY OR PAINT WITH ONE COAT ZINC CHROMATE OR RED LEAD PRIMER (INDUSTRIAL QUALITY). OVERCOAT WITH GREY INDUSTRIAL ENAMEL SECT. 790.
2. SHAPE, COMPACT AND PLASTER NEW DITCH FROM HEADWALL TO UNDISTURBED EXISTING DITCH. PLASTER TO EXTEND TO MINIMUM ELEVATION NOTED 1000 mm BEYOND CONNECTION TO UNDISTURBED EXISTING DITCH.
3. ELEVATIONS A, B, C & D AND DIMENSIONS E, F, G, H, I, J, K, L & M WILL BE SHOWN ON PLANS. DIMENSIONS SHOULD PROVIDE STANDARD SIZE BLOCK.
4. 350 mm PLATE SHALL NOT EXTEND BELOW TOP OF PIPE.



### SECTION A-A

DETAIL NO.  
**502-1**



**STANDARD DETAIL  
METRIC**

**TRASH RACK**

REVISED  
**3-10-2000**

DETAIL NO.  
**502-1**



3.5 mm SHEET  
STEEL COVER —

HANDLE EXTENDS  
150 mm BELOW  
TOP WHEN GATE  
IS OPEN

STANDARD  
CONCRETE  
PIPE \_\_\_\_\_

CONCRETE AS  
REQUIRED TO  
SECURE GATE

FINISH  
GRADE

VARIABLE

1. BRACE TO BE INSTALLED EVERY 600 mm FROM TOP OF HEADGATE FRAME. BOTTOM BRACE TO BE HIGH ENOUGH TO ENABLE FULL OPENING OF HEADGATE.

2. INSTALL 12.7 mm BOLTS INTO LEAD PLUG DRILLED TO WITHIN 25 mm OF OUT SIDE OF STANDPIPE. SPACERS TO BE INSTALLED AT EACH BOLT BETWEEN HEADGATE FRAME AND INSIDE OF STAND PIPE.

3. LOCATION OF 50 mm HOLE FOR GATE STEM TO BE DETERMINED AFTER INSTALLATION OF GATE.

— SEE NOTE 3

—(4) 9.5 mm BOLTS TO BE  
GROUTED INTO STANDPIPE  
EQUIDISTANT WITH  
38x75 mm RECTANGULAR  
WASHERS AND NUTS

— GALVANIZED EXPANDED  
METAL LID (3.9 mm)

SEE NOTE 2 -

REINF. CONC.  
PIPE \_\_\_\_\_

SEE NOTE 1

GROUT JOINTS  
WATER TIGHT —

VARIABLES	1200 MIN.	1300 MAX.
-----------	-----------	-----------

—FINISH  
GRADE

— 25 mm C.R.S.  
LIFT ROD

— HEADGATE TO  
BE SWANSON  
800 SERIES  
OR APPROVED  
EQUAL

FORM CONC. AROUND  
END OF PIPE BEHIND  
HEADGATE FRAME

NOTE:  
PAINT ARROW ON OUTSIDE OF  
STANDPIPE INDICATING DIRECTION  
"TO OPEN" HEADGATE.

TYPE 'B'

—CLASS 'A'  
CONCRETE AS  
PER SECT. 725

DETAIL NO.

503



## STANDARD DETAIL METRIC

## IRRIGATION STANDPIPE

REVISÉ

**3-10-2000**

DETAIL NO.


503



## NOTES:

1. A CONCRETE COLLAR IS REQUIRED WHERE PIPES OF DIFFERENT DIAMETERS OR MATERIALS ARE JOINED, OR WHERE THE CHANGE IN ALIGNMENT OR GRADE EXCEEDS THAT ALLOWED FOR ON ORDINARY JOINTS.
2. WHERE PIPES OF DIFFERENT DIAMETERS ARE JOINED WITH A CONCRETE COLLAR, L AND T SHOULD BE THOSE OF THE LARGER PIPE.  $D=D-1$ , OR  $D-2$  WHICHEVER IS GREATER.
3. FOR PIPE SIZES NOT LISTED USE NEXT SIZE LARGER.
4. OMIT REINFORCING ON PIPE 600 mm OR LESS IN DIAMETER.
5. WHERE REINFORCING IS REQUIRED, THE DIAMETER OF THE CIRCULAR TIES SHALL BE...  
OUTSIDE DIAMETER OF PIPE+T.
6. FIELD CLOSURES OF PIPE OF THE SAME DIAMETER AND WITHOUT CHANGE IN GRADE OR ALIGNMENT SHALL BE MADE WITH A CONCRETE COLLAR.

A\*=ANGLE OF DEFLECTION



TABLE

D	L	T
300	300	100
450	300	125
600	300	150
900	450	200
1200	450	250
1425	450	250
1500	475	275
1650	475	275

DETAIL NO.

505



STANDARD DETAIL  
METRIC

CONCRETE PIPE COLLAR


REVISED

3-10-2000

DETAIL NO.

505

NOTE:  
CONTRACTOR MAY USE PRECUT FITTINGS IF DESIRED.  
BID ITEM INCLUDES LATERAL PIPE, RISER, PAD, VALVE,  
LABOR AND INCIDENTAL MATERIAL REQUIRED FOR  
INSTALLATION.



DETAIL NO.

506



**STANDARD DETAIL  
METRIC**

**IRRIGATION VALVE INSTALLATION**

REVISED


3-10-2000

DETAIL NO.


506

## NOTES:

1. THIS DETAIL SHALL BE REQUIRED WHEN NEW OR EXISTING PIPE INSTALLATIONS WILL BE SUBJECT TO DAMAGE ANYTIME IN THE FUTURE DUE TO LACK OF PROPER COVER, AS DETERMINED BY THE ENGINEER.
2. FOR PIPE OVER 450 mm I.D. WOOD, METAL OR GYPSUM BOARD FORMS MUST BE USED TO FORM THE SIDES OF THE ENCASEMENT. GYPSUM BOARD FORMS MAY BE LEFT IN THE GROUND BELOW THE TOP OF THE ENCASEMENT. THIS SHALL BE OPTIONAL WITH POURING AGAINST TRENCH WALLS FOR ENCASEMENT OF 450 mm AND SMALLER PIPE.
3. FOR ALL SITUATIONS WHERE SIDE FORMS ARE USED, TRENCH WALLS SHALL BE OVER-EXCAVATED TO ALLOW SUFFICIENT ROOM TO OPERATE PROPER MECHANICAL COMPACTION EQUIPMENT.
4. CONCRETE WHICH SPILLS BEYOND 300 mm FROM THE SIDES OF THE PIPE FOR ANY REASON SHALL BE REMOVED BACK TO THE PROPER LINE PRIOR TO BACKFILLING.
5. SEE SECT. 601 FOR TRENCH PREPARATION. CONCRETE TO BE CLASS 'A' PER SECT. 725.
6. COVER TO BE APPROVED BY ENGINEER.



LONGITUDINAL SECTION



END SECTION

DETAIL NO.

507



**STANDARD DETAIL  
METRIC**

**ENCASED CONCRETE PIPE  
(FOR SHALLOW INSTALLATION)**


REVISED

3-10-2000

DETAIL NO.


507







### CONNECTOR CROSS SECTION

NOTE:  
USE 16 mm WASHER AND NUT,  
ALL PIECES (NUTS, WASHERS,  
AND FABRICATED BOLTS) TO  
BE GALVANIZED AS PER  
A.S.T.M. A-123 LATEST  
REVISION.





WELD ALL  
AROUND

### T-BOLT



### SECTION A-A



DETAIL NO.

510



STANDARD DETAIL  
METRIC



CORRUGATED METAL PIPE  
AND INSTALLATION

REVISED

3-10-2000


DETAIL NO.

510



## NOTES

1. ALL CONCRETE TO BE CLASS 'A' PER SECT. 725, 505.
2. MATCH SPRING LINES OF PIPE ENTERING MANHOLE UNLESS OTHERWISE NOTED.
3. CUT PIPES TO ALLOW SETTING OF 1220 mm DIA. CYLINDRICAL FORM FROM 150 mm ABOVE MAIN LINE PIPE TO SPRING LINE. CUT PIPE 50 mm LARGER THAN FORM TO ALLOW 50 mm CONCRETE OVER ENDS OF ALL CUT PIPE.
4. INVERT AND BASE OF MANHOLE TO BE POURED AND INVERT TO BE SHAPED BY HAND TO MAKE SMOOTH TRANSITION. FINISH WITH RUBBER FLOAT.
5. CENTER MANHOLE ON PIPE JOINT WHERE PIPE CHANGES SIZES, LEAVING A GAP OF 300 mm MINIMUM, 600 mm MAXIMUM.



DETAIL NO.

520



**STANDARD DETAIL  
METRIC**


**STORM DRAIN MANHOLE BASE  
(1220 mm AND SMALLER)**

REVISED

3-10-2000

DETAIL NO.

520





### NOTES:

1. LINE PIPE AND STUB MAY BE CAST MONOLITHICALLY OR STUB MAY BE CAST ON TO LINE PIPE SECTION PRIOR TO COMPLETE CURING.
2. ALL LINE PIPE REINFORCEMENT SHALL BE TURNED UP INTO STUB.
3. THE VERTICAL STUB TO BE A.S.T.M. C-76 CLASS II WALL 'A' AND THE HORIZONTAL PIPE TO BE EQUAL TO STRENGTH OF PIPE ENTERING MANHOLE.
4. ALL REINFORCING STEEL SHALL CLEAR FACE OF CONCRETE BY 40 mm UNLESS SHOWN OTHERWISE.
5. CONCRETE ENCASEMENT SHALL BE CLASS 'A' PER SECT. 725, 505.

TABLE OF VALUES FOR 'F' & 'D'

*'D'(mm)	1295	1372	1448	1524	1600	1676	1753	1829	1981	2134	2286	2438
'F'(mm)	350	370	380	395	415	425	445	455	490	520	550	580

\*TRUE INNER DIAMETER DIMENSIONS. (NOT NOMINAL SIZE.)



DETAIL NO.

521



STANDARD DETAIL  
METRIC


STORM DRAIN MANHOLE BASE  
(1295 mm OR LARGER)

REVISED


3-10-2000

DETAIL NO.

521




**VERTICAL SECTION OF  
ECCENTRIC MANHOLE SHAFT**



**PLAN**

USE WHERE THERE IS 1170  
OR LESS COVER OVER PIPE




**SECTION B-B**

**SHALLOW MANHOLE**

**NOTES:**

1. PRECAST CONCRETE CONES AND SECTIONS TO BE A.S.T.M. C-478M.
2. BRICK MAY BE USED IN LIEU OF, OR IN COMBINATION WITH CONCRETE ADJUSTING RINGS.
3. PRECAST CONCRETE SECTIONS 1200 mm DIA. PIPE MAY BE FURNISHED IN STANDARD LENGTHS.
4. UNLESS OTHERWISE SHOWN ON PLANS, USE 2-65 mm PRECAST CONCRETE ADJUSTING RINGS ON IMPROVED STREETS AND 4-65 mm RINGS ON UNIMPROVED STREETS.
5. MANHOLE STEPS SHALL BEGIN 600 mm BELOW FINISHED GRADE AND CONTINUE AT 300 mm INTERVALS TO APPROXIMATELY 600 mm ABOVE MANHOLE SHELF. (AS REQUIRED BY AGENCY.)



65 mm RINGS SHALL BE REINFORCED WITH TWO 6.3 mm ROUND STEEL HOOPS; 150 AND 200 mm RINGS SHALL BE REINFORCED WITH FOUR 6.3 mm HOOPS, TIED WITH 2 mm WIRE 200 mm O.C.

**REINFORCED CONCRETE  
ADJUSTING RING**

DETAIL NO.

**522**



**STANDARD DETAIL  
METRIC**

**STORM DRAIN MANHOLE SHAFT**

REVISED


**3-10-2000**

DETAIL NO.

**522**




FOR A 610 mm M.H. OPENING, MODIFY THE STD. 610 mm  
M.H. FRAME & COVER, FOLLOWING THE NOTED PROCEDURES,  
ONE THRU FIVE.



- ① DRILL (8) HOLES 13.5 mm IN COVER FOR 12.7 mm CAPSCREWS, COUNTERBORE 13 mm DEEP BY 29 mm DIA. TO ACCOMMODATE CAPSCREW AND SOCKET WRENCH. SPACE EQUALLY.
  - ② DRILL (8) HOLES AND TAP FOR 12.7 mm – 13 THREAD NATIONAL COARSE BOLT.
  - ③ DRILL, TAP AND COUNTERBORE (2) HOLES FOR 12.7 mm CAPSCREWS TO BE USED FOR LIFTING COVER. PLUG WITH CAPSCREWS.
  - ④ COVER AND FRAME MUST BE MATCHED, DRILLED AND TAPPED IN SETS.
  - ⑤ CASTING DIMENSIONS GIVEN ABOVE ARE FROM DET. 424, 610 mm MANHOLE FRAME AND COVER.
- BOTH 610 & 760 mm FRAMES TO BE ANCHORED AS FOLLOWS:
- ⑥ DRILL 13 mm HOLE IN FILLET. DO NOT USE ADJACENT FILLETS.
  - ⑦ 6 mm STAINLESS STEEL CABLE. SECURED WITH CABLE CLAMPS.
  - ⑧ 13x225 mm HOOK AND EYE TURNBUCKLE.
  - ⑨ 13 mm EYE BOLT WITH 25 mm DIA. EYE.
  - ⑩ INSTALL THREE CABLES PER 610 mm (FOUR CABLES FOR 760 mm COVERS). EYEBOLTS TO BE SET DIRECTLY BELOW FILLETS USED.
  - ⑪ TRIPLE WRAP TURNBUCKLES AND CABLE CLAMPS WITH 25 mm WIDE TAPE, SAFE-T-CLAD, F.O.S. 655, OR APPROVED EQUAL.


GROUND MATCH MARK  
6 mm W x 3 mm D

(2) CONCEALED  
PICKHOLES  
180 DEG. APART




### NOTES:

1. DRILL (6) HOLES IN 760 mm COVER (4 HOLES IN 610 mm COVER) 13 mm CORED RECESS FOR 13 mm CAPSCREWS. SPACE EQUALLY (304 S.S.)
2. DRILL (6) HOLES IN 760 mm FRAME (4 HOLES IN 610 mm FRAME) AND TAP FOR 13 mm – NATIONAL COARSE BOLT (HEX HEAD).
3. COVER AND FRAME MUST BE MATCH MARKED, DRILLED AND TAPPED IN SETS.
4. DIMENSIONS, LETTERING, WEIGHTS AND MATERIALS SHALL CONFORM TO DET. 424.
5. REFER TO DETAIL 523-1 FOR INSTALLATION PROCEDURES.




BOLT HOLE DETAIL



PICKHOLE DETAIL

### COVER SECTION

TYP. BOLT PAD



19 mm DIA. CORED  
HOLES IN GUSSET

### FRAME SECTION

DETAIL NO.

523-2



STANDARD DETAIL  
METRIC

PRESSURE MANHOLE


REVISED

3-10-2000


DETAIL NO.

523-2

TOP VIEW




SECTION A-A



SIDE INLET  
TYPE "1"

FRONT VIEW



CATCH BASIN ABOVE STORM DRAIN  
TYPE "2"

NOTES:

1. 'D' SHALL BE 610 mm OR LESS. FOR LARGER VALUE OF 'D' USE MANHOLE OR JUNCTION STRUCTURE.
2. IN NO CASE SHALL THE OUTSIDE DIAMETER OF THE INLET EXCEED ONE HALF THE INSIDE DIAMETER OF THE MAIN STORM DRAIN.
3. CENTERLINE OF INLET SHALL BE ON RADIUS OF MAIN STORM DRAIN EXCEPT WHEN ELEVATION 'S' IS SHOWN ON PLANS.
4. THE MINIMUM OPENING INTO THE STORM DRAIN SHALL BE THE OUTSIDE DIAMETER OF THE CONNECTING PIPE PLUS 25 mm.
5. IF ANGLE X IS 45° OR LESS USE TYPE 1.

DETAIL NO.

524



**STANDARD DETAIL**  
**METRIC**


**STORM DRAIN LATERAL**  
**PIPE CONNECTIONS**

REVISED


3-10-2000

DETAIL NO.


524



**SECTION A-A**



**SECTION B-B**



**PLAN VIEW**

### NOTES:

1. THE ENTIRE CATCH BASIN COVER MAY BE POURED IN PLACE OR PRECAST.
2. CONNECTION PIPES MAY BE PLACED IN ANY POSITION AROUND THE WALLS PROVIDED THE POSITION IS CONSISTENT WITH THE PLAN.
3. OUTLET PIPE SHALL BE TRIMMED TO FINAL SHAPE AND LENGTH BEFORE CONCRETE IS POURED.
4. FLOOR OF BASIN SHALL BE TROWELLED TO A HARD SMOOTH SURFACE AND SHALL SLOPE FROM ALL DIRECTIONS TO OUTLET.
5. ALL STRUCTURAL STEEL TO BE PAINTED ONE SHOP COAT OF NO. 1 D PAINT AND TWO FIELD COATS OF NO. 10 PAINT AS PER SECT. 790.

### DIMENSIONS

T=150 mm IF V=1220 mm OR LESS  
T=200 mm IF V IS BETWEEN 1220 AND 2440 mm.  
T=250 mm IF V IS 2440 OR MORE (IF V EXCEEDS  
3000 mm SPECIAL DESIGN IS REQUIRED)  
V=1070 mm UNLESS OTHERWISE SPECIFIED.

CURB	A
100	990
150	535
175	305

\* SEE DETAILS 536-1 AND 536-2 FOR DETAILS AND SECTIONS COMMON TO ALL CURB OPENING CATCH BASINS.

\*\* 1200 mm LOCATIONS WHERE 1200 mm S/W IS REQUIRED.

DETAIL NO.

**530**



**STANDARD DETAIL  
METRIC**

**1070 mm CURB OPENING  
CATCH BASIN - TYPE 'A'**


REVISED

**3-10-2000**


DETAIL NO.

**530**






**SECTION A-A**



**SECTION B-B**



**PLAN VIEW**

**NOTES:**

1. THE ENTIRE CATCH BASIN COVER MAY BE POURED IN PLACE OR PRECAST.
2. CONNECTION PIPES MAY BE PLACED IN ANY POSITION AROUND THE WALLS PROVIDED THE POSITION IS CONSISTENT WITH THE PLAN.
3. OUTLET PIPE SHALL BE TRIMMED TO FINAL SHAPE AND LENGTH BEFORE CONCRETE IS POURED.
4. FLOOR OF BASIN SHALL BE TROWELLED TO A HARD SMOOTH SURFACE AND SHALL SLOPE FROM ALL DIRECTIONS TO OUTLET.
5. ALL STRUCTURAL STEEL TO BE PAINTED ONE SHOP COAT OF NO. 1 D PAINT AND TWO FIELD COATS OF NO. 10 PAINT AS PER SECT. 790.

**DIMENSIONS**

T=150 mm IF V=1220 mm OR LESS  
T=200 mm IF V IS BETWEEN 1220 AND 2440 mm.  
T=250 mm IF V IS 2440 mm OR MORE  
(IF V EXCEEDS 3000 mm  
SPECIAL DESIGN IS REQUIRED)  
V=1070 mm UNLESS OTHERWISE SPECIFIED.

CURB	A
100	990
150	535
175	305

\* SEE DETAILS 536-1 AND 566-2 FOR DETAILS AND SECTIONS COMMON TO ALL CURB OPENING CATCH BASINS.

\*\*1200 mm LOCATIONS WHERE 1200 mm S/W IS REQUIRED.

DETAIL NO.

**531**



**STANDARD DETAIL  
METRIC**




**1680 mm CURB OPENING  
CATCH BASIN - TYPE 'B'**

REVISED

**3-10-2000**

DETAIL NO.

**531**



### NOTES:

1. THE ENTIRE CATCH BASIN COVER MAY BE POURED IN PLACE OR PRECAST.
2. CONNECTION PIPES MAY BE PLACED IN ANY POSITION AROUND THE WALLS PROVIDED THE POSITION IS CONSISTENT WITH THE PLAN.
3. OUTLET PIPE SHALL BE TRIMMED TO FINAL SHAPE AND LENGTH BEFORE CONCRETE IS POURED.
4. FLOOR OF BASIN SHALL BE TROWELLED TO A HARD SMOOTH SURFACE AND SHALL SLOPE FROM ALL DIRECTIONS TO OUTLET.
5. ALL STRUCTURAL STEEL TO BE PAINTED ONE SHOP COAT OF NO. 1 D PAINT AND TWO FIELD COATS OF NO. 10 PAINT AS PER SECT. 790.

CURB	A
100	990
150	535
175	305

### DIMENSIONS

T=150 mm IF V=1220 mm OR LESS  
T=200 mm IF V IS BETWEEN 1220 AND 2440 mm.  
T=250 mm IF V IS 2440 mm OR MORE  
(IF V EXCEEDS 3000 mm  
SPECIAL DESIGN IS REQUIRED)  
V=1070 mm UNLESS OTHERWISE SPECIFIED.

\*SEE DETAILS 536-1 AND 536-2 FOR DETAILS AND SECTIONS COMMON TO ALL CURB OPENING CATCH BASINS.  
\*\*1200 mm LOCATIONS WHERE 1200 mm S/W IS REQUIRED.

DETAIL NO.

532



STANDARD DETAIL  
METRIC


2440 mm CURB OPENING  
CATCH BASIN - TYPE 'C'

REVISED

3-10-2000

DETAIL NO.


532



GRATE AND FRAME  
SEE DETAIL 533-3  
& 533-4

NOTE: REINFORCING BARS SHOWN ARE FOR ROOF SLAB ONLY.  
SEE NOTE NO. 5 AND SECTIONS FOR OTHER REINFORCING.


### PLAN VIEW



### SECTION A-A

### NOTES:


1. SINGLE C.B. (ILLUSTRATED), SUMP WITH WING BASIN UPSTREAM.
2. DOUBLE C.B. SUMP WITH SYMMETRICAL WING BASINS EACH SIDE.
3. PIPES CAN BE PLACED IN ANY WALL EXCEPT WALL ADJACENT TO A WING BASIN. PIPE SHALL BE TRIMMED TO FINAL SHAPE AND LENGTH BEFORE CONCRETE IS PLACED.
4. SUMP FLOOR SHALL HAVE A WOOD TROWEL FINISH AND A MIN. SLOPE OF 4:1 IN ALL DIRECTIONS TOWARD OUTLET PIPE.
5. ALL REFORCING BARS SHALL BE 15M 450 mm C TO C BOTH WAYS AND 40 mm CLEAR TO INSIDE OF WALLS AND OUTSIDE WING BASIN FLOOR EXCEPT AS SHOWN. SEE SECT. 727.
6. ALL CONCRETE SHALL BE CLASS 'A', PER SECT. 725.
7. CONSTRUCTION JOINTS SHALL BE PLACED TO MEET FIELD CONDITIONS.
8. ALL EXPOSED STEEL SHALL BE GALVANIZED OR PAINTED WITH ONE SHOP COAT OF #1 PAINT AND TWO FIELD COATS OF #10 PAINT.



### SECTION B-B

### DIMENSIONS

V = 1000 mm MIN. WHEN L = 1000 mm  
V = 1050 mm MIN. WHEN L = 2000 mm  
V = 1100 mm MIN. WHEN L = 3000 mm  
V = 1200 mm MIN. WHEN L = 5000 mm  
T = 150 mm WHEN V IS LESS THAN 2400 mm  
T = 200 mm WHEN V IS EQUAL TO OR GREATER THAN 2400 mm  
H = CURB HEIGHT PRIOR TO THE TRANSITION



### REINFORCEMENT DETAIL

DETAIL NO.

533-1



STANDARD DETAIL  
METRIC

CATCH BASIN TYPE 'D'


REVISED

3-10-2000


DETAIL NO.

533-1

533-2




**FRAME DETAIL**




## FRAME AND GRATE NOTES

14. FRAME AND GRATING SHALL BE TESTED FOR ACCURACY OF FIT AND SHALL BE MARKED IN SETS BEFORE DELIVERY.
15. ALL WELDING SHALL BE IN ACCORDANCE WITH STANDARD WELDING SPECIFICATIONS.
16. CROSS BARS AND END BARS MAY BE FILLET WELDED, RESISTANCE WELDED OR ELECTRO FORGED TO BEARING BARS.
17. ANCHORS SHALL BE 9.5 mm DIA. STEEL ROD, 10M REBAR, 9.5 mm DIA. x 200 mm BOLTS OR 200mm NELSON STUDS.
18. ALL PARTS SHALL BE OF STRUCTURAL GRADE STEEL.
19. ALL EXPOSED STEEL SHALL BE GALVANIZED OR PAINTED WITH ONE COAT #1 PAINT AND TWO FIELD COATS OF #10 PAINT.



**GRATE DETAIL**



**SECTION F-F**

DETAIL NO.

533-3



STANDARD DETAIL  
METRIC


FRAME AND GRATE FOR TYPE 'D' CATCH BASIN

DETAIL NO.

3-10-2000


DETAIL NO.

533-3



**GRATE DETAIL**

GRATE OPENING: 0.404 m<sup>2</sup>



**SECTION B-B**

DETAIL NO.  
**533-4**




**STANDARD DETAIL**  
**METRIC**


**2130 mm CURB OPENING CATCH BASIN**  
**TYPE 'D' - GRATE DETAILS**

REVISED  
**3-10-2000**

DETAIL NO.  
**533-4**



GRATE OPENING: 0.404 m<sup>2</sup>



**SECTION B-B**

DETAIL NO.  
**533-4**




**STANDARD DETAIL  
METRIC**


**2130 mm CURB OPENING CATCH BASIN  
TYPE 'D' - GRATE DETAILS**

REVISED  
**3-10-2000**

DETAIL NO.  
**533-4**



**SECTION A-A**



**SECTION B-B**

**DIMENSION**


V=900 mm UNLESS OTHERWISE SPECIFIED.

\* DIMENSIONAL CHANGE WITH DETAIL 534-3 AND DETAIL 534-4.

NOTE:  
ALL CONCRETE, CLASS  
'A', AS PER SECT. 725

**NOTES:**

1. ADJUSTABLE CURB, FRAME AND GRATING UNITS SHALL BE STRUCTURAL STEEL OR CAST IRON.
2. PIPES MAY ENTER OR LEAVE ANY WALL. BOTTOM OF BOX TO BE SLOPED TO OUTLET PIPE FROM ALL DIRECTIONS AND TROWELLED TO A HARD SMOOTH SURFACE.
3. CONNECTION PIPES MAY BE PLACED IN ANY POSITION AROUND THE WALLS PROVIDED THE POSITION IS CONSISTENT WITH THE PLAN.
4. OUTLET PIPE SHALL BE TRIMMED TO FINAL SHAPE AND LENGTH BEFORE CONCRETE IS POURED.
5. ALL STRUCTURAL STEEL TO BE PAINTED ONE SHOP COAT OF NO. 1 PAINT AND TWO FIELD COATS OF NO. 10 PAINT AS PER SECT. 790.



**HALF PLAN GUTTER & GRATE**

**HALF PLAN FRAME & ANCHORS**

DETAIL NO.

**534-1**



**STANDARD DETAIL  
METRIC**

**CATCH BASIN TYPE 'E'**


REVISED

**3-13-2000**


DETAIL NO.

**534-1**








**CROSS SECTION**




**GRATE**



**ANCHOR**



**ADJUSTABLE CURB**



**COMPOSITE VIEW**

DETAIL NO.

**534-2**



**STANDARD DETAIL  
METRIC**



**CATCH BASIN TYPE 'E' (DETAILS)**

REVISED

**3-13-2000**


DETAIL NO.

**534-2**




**SECTION A-A**

**CAST IRON FRAME – GRATE – CURB BOX**



**SECTION B-B**



**VANE DETAIL**

**NOTE:**

DIMENSIONAL CHANGE REQUIRED FROM 1041 mm  
WIDTH TO 915 mm, AND 533 mm DEPTH TO 610 mm.  
MATERIAL CAST GRAY IRON ASTM A-48 CLASS 35B.  
FRAME WEIGHT 95 kg; GRATE 64 kg; CURB BOX 42 kg.

DETAIL NO.  
**534-3**





**STANDARD DETAIL  
METRIC**

**CATCH BASIN TYPE 'E' (DETAILS)**


REVISED  
**3-13-2000**

DETAIL NO.  
**534-3**




**SECTION A-A**

**DOUBLE UNIT CAST IRON FRAME — GRATE — CURB BOX**



**SECTION B-B**



**VANE DETAIL**

**NOTE:**

DIMENSIONAL CHANGE REQUIRED FROM 1041 mm WIDTH TO 1880 mm, AND 533 mm DEPTH TO 610 mm. REQUIRES ONE CENTER STEEL I-BEAM S100x11. MATERIAL CAST GRAY IRON ASTM A-48 CLASS 35B. FRAME MASS 89 kg; GRATE 64 kg; CURB BOX 42 kg.

DETAIL NO.  
**534-4**









**STANDARD DETAIL  
METRIC**

**CATCH BASIN TYPE 'E' (DETAILS)**

REVISED  
**3-13-2000**

DETAIL NO.  
**534-4**



DETAIL NO.  
**534-5**





**STANDARD DETAIL  
METRIC**


**ALTERNATE GRATE STYLES  
SUMP LOCATION**

REVISED  
**3-13-2000**

DETAIL NO.  
**534-5**



**SECTION A-A**



**GRATE**

**NOTES:**

1. PIPES MAY ENTER OR LEAVE ANY WALL. BOTTOM OF BOX TO BE SLOPED TO OUTLET PIPE FROM ALL DIRECTIONS AND TROWELLED TO A HARD SMOOTH SURFACE.
2. CONNECTION PIPES MAY BE PLACED IN ANY POSITION AROUND THE WALLS PROVIDED THE POSITION IS CONSISTENT WITH THE PLAN.
3. OUTLET PIPE SHALL BE TRIMMED TO FINAL SHAPE AND LENGTH BEFORE CONCRETE IS POURED.
4. ALL STRUCTURAL STEEL TO BE PAINTED ONE SHOP COAT OF NO. 1 PAINT AND TWO FIELD COATS OF NO. 10 PAINT AS PER SECT. 790.
5. ALL WELDS ON FRAME AND SIDE BARS ON GRATE SHALL BE FULL LENGTH OF JOINT.

NOTE:  
CONSTRUCT BOX AS PER CATCH BASIN TYPE 'E'  
(LOWER PORTION ONLY).

DETAIL NO.

**535**



**STANDARD DETAIL  
METRIC**


**CATCH BASIN TYPE 'F'  
(FOR USE WITHOUT CURB)**

REVISED

3-13-2000


DETAIL NO.

**535**




### SECTION C-C

FOR DETAILS 531, 532 AND 533




### SECTION D-D




### PROTECTION BAR

### NOTES:

- 1) HORIZONTAL PLAIN ROUND GALVANIZED STEEL PROTECTION BAR SHALL BE USED WHEN CURB FACE IS 230 mm OR MORE.
- 2) THE BAR SHALL BE EMBEDDED 125 mm AT EACH END.



### PLAN VIEW



### DOWEL BAR

DETAIL NO.

536-1



STANDARD DETAIL  
METRIC


COMMON DETAILS AND SECTIONS  
FOR CURB OPENING CATCH BASINS

REVISED


3-13-2000

DETAIL NO.

536-1




**PLAN VIEW**




- 1 EACH 304-S.STL. SPRING  
63x13.5 I.D.x2.4
- 2 EACH 13 mm HEX NUT
- 3 EACH 13 mm FLAT WASHER
- 1 EACH 13 mm LOCK WASHER


**DROP HANDLE**



**SECTION B-B**



**SECTION A-A**



**SECTION C-C**

**NOTES:**

- 1. FRAME SHALL BE NON-LOCKING.
- 2. FRAME AND COVER SHALL BE CAST IRON OR ASTM A-36 STRL. HORIZONTAL SURFACE OF COVER IN CONTACT WITH FRAME SHALL BE MACHINED. ASA B-46 ROUGHNESS SHALL NOT EXCEED 0.79 mm.
- 3. COVER SHALL BE FILLED WITH CONCRETE AND BROOM FINISHED.
- 4. SMALL VARIATIONS IN DIMENSIONS OF FEATURES OF A MINOR NATURE THAT ARE PART OF THE FOUNDRY'S CASTING ARE PERMISSIBLE.

DETAIL NO.

**536-2**



**STANDARD DETAIL  
METRIC**



**ALTERNATE COVER FOR  
CURB OPENING CATCH BASINS**

REVISED

**3-13-2000**


DETAIL NO.

**536-2**





**DETAIL OF ANGLE FRAME  
GRATE SUPPORT**

ALL CONCRETE SHALL BE  
CLASS 'A' PER SECT. 725.  
EXPOSED EDGES SHALL BE  
FINISHED WITH A 13 mm  
RADIUS.



**BAR GRATE**  
SEE DETAIL 539



**SECTION C-C**

DETAIL NO.

**537**



STANDARD DETAIL  
METRIC

**CATCH BASIN - TYPE 'G'**


REVISED

7-05-2000

DETAIL NO.

**537**





WHEN DOUBLE GRATE IS USED  
INCREASE THE LENGTH OF THE  
STRUCTURE ACCORDINGLY.


CUT HOLE IN PIPE 600 mm LONG  
FOR SINGLE GRATE STRUCTURES  
AND 1200 mm LONG FOR DOUBLE  
GRATE. WIDTH DEPENDS ON DIA.  
OF PIPE, NOT TO EXCEED 560 mm  
MIN. WIDTH TO BE SET BY PROJECT  
ENGINEER.

SEE DETAIL 539 FOR GRATE


725x725 mm I.D. SINGLE FRAME  
725x1325 mm I.D. DOUBLE FRAME

L76x76x13  
ANGLE  
IRON FRAME

M14x150 mm  
LUGS WELDED  
TO FRAME, 4  
EACH - 1 ON  
EACH CORNER  
OF FRAME




**DETAIL OF ANGLE  
FRAME GRATE SUPPORT**




**SECTION A-A**

THESE DIMENSIONS VARY  
WITH DEPTH AND DIA. OF PIPE



**SECTION A-A**



**SECTION A-A**  
600 mm PIPE (NOMINAL)

DETAIL NO.

**538**



STANDARD DETAIL  
METRIC


**CATCH BASIN - TYPE 'H'**

REVISIONS

3-13-2000

DETAIL NO.

**538**



### NOTES:

1. ALL STEEL SHALL BE IN ACCORDANCE WITH A.S.T.M. A-36.
2. WELDING SHALL BE IN ACCORDANCE WITH A.W.S. SPECIFICATIONS.
3. FRAME AND GRATE SHALL BE TESTED FOR ACCURACY OF FIT AND SHALL BE MARKED IN SETS BEFORE DELIVERY.
4. THE COMPLETED ASSEMBLY SHALL BE GIVEN ONE SHOP COAT OF NO. 1 PAINT AND TWO FIELD COATS OF NO. 10 PAINT AS PER SECTION 790.
5. THE GRATE SHALL BE FABRICATED TO WITHIN 3 mm SPECIFIED DIMENSIONS.

DETAIL NO.

539



STANDARD DETAIL  
METRIC


GRATES FOR CATCH BASINS,  
TYPE G AND H

REVISED


3-13-2000

DETAIL NO.


539




**PLAN I**



**SECTION B-B**




**PLAN IA**





**SECTION C-C**

GRATE TYPES TW-1 AND TW-2



**PLAN IB**



**SECTION A-A**

GRATE TYPES TB-1 AND TB-2

BAR TABLE				
TYPE	CLEAR SPACING	NO. BARS	X	GRATE OPENING m <sup>2</sup>
TW OR TB-1.0	25	26	30	0.298
TW OR TB-1.1	35	21	24	0.308
TW OR TB-1.2	50	16	31	0.433
TW OR TB-2.0	25	26	30	0.216
TW OR TB-2.1	35	21	24	0.224
TW OR TB-2.2	50	16	31	0.246

TW INDICATES TRANSVERSE WELDED  
TB INDICATES TRANSVERSE BOLTED

**NOTES:**

1. GRATING UNITS AND FRAMES SHALL BE FABRICATED FROM STRUCTURAL STEEL EXCEPT AS NOTED.
2. WELDING SHALL BE IN ACCORDANCE WITH STD. WELDING SPECS.
3. THE COMPLETED ASSEMBLY SHALL BE GIVEN TWO SHOP COATS OF NO. 1 PAINT AS PER SECT. 790.
4. FRAME AND GRATE SHALL FIT TO A MAX. ROCK OF 2.4 mm AT ANY POINT.
5. RESTRICT USE TO GRADES OF 3% OR LESS.

DETAIL NO.

**540-1**



**STANDARD DETAIL  
METRIC**


**CATCH BASIN GRATES**

REVISED


**3-13-2000**

DETAIL NO.


**540-1**




**PLAN II**



**PLAN IIA**




**PLAN IIB**




**PLAN II**


10 mm ANCHOR  
DELETE ON END  
WHEN USED WITH  
I BEAM SUPPORT




**SECTION C-C**



**SECTION D-D**




**SECTION A-A**



**SECTION B-B**

**NOTES:**

1. LW INDICATES LONGITUDINAL WELDED.
2. LB INDICATES LONGITUDINAL BOLTED.
3. EF INDICATES ELECTROFORGED.
4. GRATING UNITS AND FRAMES SHALL BE FABRICATED FROM STRUCTURAL STEEL 'A-36/A36M' EXCEPT AS NOTED.
5. ALL WELDING SHALL BE IN ACCORDANCE WITH STANDARD WELDING SPECIFICATIONS.
6. THE COMPLETED ASSEMBLY SHALL BE GIVEN ONE SHOP COAT OF NO. 1 PAINT.
7. FRAMES AND GRATES SHALL FIT TO A MAXIMUM ROCK OF 2.4 mm AT ANY POINT.
8. GRATE TYPE LW AND EF RESTRICTED TO SLOPES OF 3% OR LESS
9. GRATES TYPE LB USE LONGITUDINAL GRADES IN EXCESS OF 3% OR AS AN ALTERNATE TO TYPES LW OR EF ON GRADES OF 3% OR LESS.



**BAR SPACER DETAIL**

CAST IRON, CAST STEEL  
OR STEEL BAR STOCK

GRATE TYPE	CLEAR BAR SPACING	NO. BARS	X	GRATE OPENING m <sup>2</sup>
LW OR LB-1.0	25	16	11	0.369
LW OR LB-1.1	35	13	7	0.403
LW OR LB-1.2	50	9	43	0.450
EF-1	41	13	12	0.433
LW OR LB-2.0	25	12	9	0.277
LW OR LB-2.1	35	9	25	0.311
LW OR LB-2.2	50	7	28	0.335
EF-2	41	10	6	0.323

DETAIL NO.

**540-2**



**STANDARD DETAIL  
METRIC**

**CATCH BASIN GRATES**


REVISED

**3-13-2000**


DETAIL NO.

**540-2**


NOMINAL PIPE SIZE	PIPE DIA. (mm)	APPROX. MASS (kg)	DIMENSIONS – MILLIMETERS						APPROX. SLOPE
			T	A	B	C	E	F	
600	610	690	75	841	1105	762	1867	1219	3
675	690	875	83	267	1257	610	1867	1372	3
750	760	990	89	305	1372	502	1873	1524	3
900	910	1860	102	381	1600	883	2483	1829	3
1050	1070	2440	114	533	1600	889	2489	1981	3
1200	1220	2970	127	610	1829	660	2489	2134	3
1350	1370	3740	140	686	1651	845	2496	2286	2 1/2




PLAN




SPACING FOR MULTIPLE  
INSTALLATION




SECTION A-A



FRONT ELEVATION



RIGHT ANGLE CULVERT



SKEWED CULVERT

## NOTES

1. DESIGN OF END SECTION SHALL CONFORM TO STANDARD FOR REINFORCED CONCRETE PIPE.
2. END SECTION JOINT CONFORMATION SHALL MATCH THE PIPE JOINTS.
3. EMBANKMENT SLOPE SHALL BE WARPED TO MATCH SLOPE OF END SECTION.
4. CULVERT LENGTH IS AS SHOWN ON PLANS.

DETAIL NO.

**545**



**STANDARD DETAIL  
METRIC**




**END SECTION-REINFORCED CONCRETE PIPE**

REVISED

**3-13-2000**




DETAIL NO.

**545**



### NOTES:

1. WHERE ROCK IS ENCOUNTERED THE OUTLET MAY BE OMITTED.
2. ALL PORTIONS OF SPILLWAY TO BE TROWEL FINISHED.
3. CONCRETE FOR THE SPILLWAY INLET, SPILLWAY AND OUTLET SHALL BE CLASS 'B' PER SECT. 725.
4. WHEN THE OUTLET IS USED, THE WIRE MESH SHALL EXTEND THROUGH THE JOINT INTO THE OUTLET IN LIEU OF BENDING INTO THE KEY.



DETAIL NO.

550



**STANDARD DETAIL  
METRIC**


**SPILLWAY INLET AND OUTLET**

REVISED


3-13-2000

DETAIL NO.

550




**DEPTH GAUGE DETAIL**  
(OPTION OF THE CONTRACTING AGENCY)




ELEVATION LOOKING UPSTREAM

1. FORD WALLS SHALL BE CLASS 'A' CONCRETE PER SECT. 725
2. DEPTH GAUGE SHALL BE PAINTED 2 COATS WHITE ENAMEL. NUMERALS AND MARKERS SHALL BE 1 COAT BLACK ENAMEL.
3. NUMBERS ON DEPTH GAUGE TO BE 50 mm HIGH.
4. HEIGHT OF DEPTH GAUGE OPTIONAL.
5. TWO DEPTH GAUGES MAY BE USED. ONE ON EACH END OF UPSTREAM WALL.




**PLAN**




**ELEVATION**

**TYPE 1 RIPRAP**



**PLAN**


Q SWALE  
OR DITCH




**ELEVATION**

**TYPE 2 RIPRAP**

## TYPICAL GABIONS



**PLAN**



**ELEVATION**

- ① HEAVY GAUGE FRAME WIRE.
- ② HEAVY GAUGE TRIPLE-TWIST HEXAGONAL MESH (OR EQUAL) FASTENED TO FRAME WIRE.
- ③ CONTINUOUS HEAVY GAUGE WRAPPED AROUND FRAMES TO FASTEN GABIONS TO EACH OTHER.
- ④ PARTITIONS TO PREVENT SHIFTING, NORMALLY ONE PER 900 mm LENGTH. INSTALLED AT FACTORY.

NOMINAL SIZE COMBINATIONS		
LENGTH	WIDTH	DEPTH
A	B	C
1830	900	300, 450, 900
2700	900	300, 450, 900
3660	900	300, 450, 900

OTHER SIZES AVAILABLE FROM MANUFACTURER.

### NOTES:

1. PLAIN ROCK OR GROUTED ROCK MAY BE SUBSTITUTED FOR SACKED CONCRETE.
2. GROUT FOR RIPRAP MAY BE PNEUMATICALLY PLACED MORTAR.

DETAIL NO.

**555**



**STANDARD DETAIL  
METRIC**

**EROSION PROTECTION / RIPRAP**

REVISED

**3-13-2000**

DETAIL NO.

**555**